

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ellis County, Sec. 8 Twp. 11S Rge. (E) 17 (W)

Location as "NE/CNW/SW" or footage from lines Cent. SW SW NE  
Lease Owner Lario Oil & Gas Company  
Lease Name Gilbert Well No. 1  
Office Address 301 S. Market, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed November 19 19 51  
Application for plugging filed August 3 19 64  
Application for plugging approved August 4 19 64  
Plugging commenced August 10 19 64  
Plugging completed August 11 19 64  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production August 3 19 64  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Kansas City Depth to top 3158 Bottom 3308 Total Depth of Well PB 3346 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13"	160	None
				8 5/8"	1117	None
				5 1/2"	3411	2215'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set plug at 3150' and run 4 sacks of cement. Pulled pipe to 700' and pumped 27 sacks of mud. Pulled pipe to 450' and pumped 20 sacks of cement. Pulled pipe to 35' and pumped 10 sacks of cement from 35' to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 18 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet.)  
Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.  
Address Box 156, Ellinwood, Kansas (Permit No. 396)


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Leo Ross (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
301 S. Market, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of August, 19 64

My commission expires July 21, 1966

Notary Public.



GILBERT #1

Operator: Lario Oil and Gas Company  
 Contractor: Stearns Petroleum, Inc.  
 Commencement Date: October 20, 1951  
 Completion Date: November 10, 1951

Location: SW/4 SW/4 NE/4,  
 Section 8-11-17, Ellis County,  
 Kansas.

Casing Record:

13-3/8" 167.98' cemented w/125 sacks  
 8-5/8" 1176.95' cemented w/875 sacks  
 5-1/2" cemented w/150 sacks

WELL LOG

Surface Clay	0	30
Sand and Clay	30	120
Sandy Shale	120	174
Blue Shale	174	305
Shale and Red Bed	305	410
Sand	410	585
Shale and Sand	585	590
Sand	590	705
Shale	705	845
Red Bed and Shale	845	1107
Anhydrite	1107	1145
Red Bed and Shale	1145	1385
Salt and Shale	1385	1630
Salt, Shale and Shells	1630	1705
Lime and Shale	1705	2965
Lime	2965	3029
Lime and Shale	3029	3062
Lime	3062	3072
Lime and Shale	3072	3101
Lime	3101	3313
Lime, Shale and Chert	3313	3370
Conglomerate	3370	3412
<u>Rotary Total Depth</u>	3412	

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 AUG 4 1964  
 CONSERVATION DIVISION  
 Wichita, Kansas

Plugged back to 3346 9-24-62

STATE OF KANSAS )  
 COUNTY OF RUSSELL) SS

I hereby certify that the above information is true and correct to the best of my knowledge.

Stearns

SUBSCRIBED AND SWORN to before me this 23rd day of November, 1951.

Paul Dalton  
 Notary Public

My Commission Expires: June 20, 1953