

Will am

- corrected -

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5145
Name: Dreiling Oil, Inc.
Address 1: P.O. Box 550
Address 2: _____
City: Hays State: Ks. Zip: 67601 + _____
Contact Person: Terry W. Piesker
Phone: (785) 652-8327
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3358 Bottom: 3400 T.D. 3400
Lansing Depth to Top: 3096 Bottom: 3215 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. ~~45~~ 12-24-48 IS-051-05266-0000
Spot Description: _____ *Klemm*
SW NE SW Sec. 14 Twp. 12 S. R. 16 East West
1,650 Feet from North South Line of Section
1,650 3030 Feet from East West Line of Section
Footages Calculated from Nearest Outside Section Corner: *per daps*
 NE NW SE SW *cell 110*
County: Ellis
Lease Name: Smith Well #: ~~21005~~ 2
Date Well Completed: 12-24-48
The plugging proposal was approved on: 6-10-10 (Date)
by: Case Morris (KCC District Agent's Name)
Plugging Commenced: 6-11-10
Plugging Completed: 6-11-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Arbuckle	oil and water	15"	30#	300'	None
Lansing-Kc	oil and water	8"	24#	3092'	None
		5 1/2"	14#	3360'	None

RECEIVED
SEP 13 2010
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tried to shoot Casing Gun- Could not get past 213'. Ran Tubing in and Casing appeared to be parted at 584'. Got through and down to 2289'. Circulated the hole with 10 Bbl. salt water down the Tubing. Pulled Tubing up to 1563' and ran strip jets- 3 holes and perforated at 1600'. Ran back to 2289' and mixed 160 sxs. 60/40 Poz, 4% Gel and cemented to surface. Pulled Tubing and tied to 4 1/2" Casing and mixed 30 sxs. Pressured to 200# and SIP- 150#. Tied to 8 5/8" Casing and mixed 35 sxs. of same and pressured to 200#. SIP- 150#. Plug job complete.

Plugging Contractor License #: 9990 Name: Allied Cementing and Acidizing, Inc.
Address 1: P.O. Box 31 Address 2: _____
City: Russell State: Kansas Zip: 67665 + _____
Phone: (785) 483-2627
Name of Party Responsible for Plugging Fees: Dreiling Oil, Inc.
State of Kansas County, Ellis, ss.
Terry W. Piesker Employee of Operator or Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Terry W. Piesker