

Handwritten initials
 Notice: Fill out COMPLETELY
 and return to Conservation Division at
 the address below within
 60 days from plugging date.

KANSAS CORPORATION COMMISSION
 OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
 K.A.R. 82-3-117

Form CP-4
 March 2009
 Type or Print on this Form
 Form must be Signed
 All blanks must be Filled

OPERATOR: License #: 6170
 Name: Globe Operating, Inc.
 Address 1: P.O. Box 12
 Address 2: _____
 City: Great Bend State: KS Zip: 67530 + _____
 Contact Person: Richard Stalcup
 Phone: (620) 792-7607
 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 185-21465 *0000* *Keep on*
 Spot Description: _____
S/2 SE NW Sec. 10 Twp. 22 S. R. 12 East West
~~4,155~~ 2825 Feet from North / South Line of Section
~~4,080~~ 3331 Feet from East / West Line of Section
 Footages Calculated from Nearest Outside Section Corner: *per ops 8/23/10*
 NE NW SE SW
 County: Stafford
 Lease Name: Spangenberg Well #: 1-10
 Date Well Completed: _____
 The plugging proposal was approved on: 08/13/2010 (Date)
 by: Richard Lacey (KCC District Agent's Name)
 Plugging Commenced: 08/19/2010
 Plugging Completed: 08/23/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8-5/8"	364'	0'
		Production	5-1/2"	3653'	1380'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

08/19/10 - Drive to location. Rig up. Sand well back to 3300'.
 08/20/10 - Drive to location. Dump bail 5 sacks cement on top of sand. Set casing jacks. Pull stretch on 5-1/2" casing - 1480' of free pipe. Clean tools. Shut down for day.
 08/23/10 - Drive to location. Rig up Log-Tech. Shot casing off @ 1380'. Rig Log-Tech down. Pull to 1st plug @ 660' w/10 sacks gel - 50 sacks 60/40 4% gel. 2nd plug @ 390' w/50 sacks 60/40 4% gel. 3rd plug @ 40' - 20 sacks 60/40 4% gel. Cement did circulate. Tally pipe - recovered 33 jts of 5-1/2" casing. Rack jacks out. Rig down. Clean tools & location.

Plugging Contractor License #: 6901 Name: D.S. & W. Well Servicing, Inc.
 Address 1: 1822 24th Street Address 2: _____
 City: Great Bend State: Kansas Zip: 67530 + _____
 Phone: (620) 793-5838
 Name of Party Responsible for Plugging Fees: Globe Operating, Inc.
 State of Kansas County, Barton, ss.
Tim Dickson Employee of Operator or Operator on above-described well,
 (Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: *Tim Dickson*

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
 SEP 13 2010
 KCC WICHITA