

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED

JUL 13 2010

Form CP-4
March 2009

Type or Print on this Form
Form must be Signed
All blanks must be Filled

KCC WICHITA

OPERATOR: License #: 5120
Name: Range Oil Company, Inc.
Address 1: 125 N. Market, Suite 1120
Address 2: _____
City: Wichita State: KS Zip: 67202 + _____
Contact Person: John Washburn
Phone: (316) 265-6231
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippian Depth to Top: 2524' Bottom: _____ T.D. 2640'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 015-22,618-0000 *see on*
Spot Description: _____
_____SW SE Sec. 9 Twp. 24 S. R. 5 East West
660 Feet from North / South Line of Section
1,720 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Butler
Lease Name: Walters B Well #: 16
Date Well Completed: 1-16-85
The plugging proposal was approved on: 6-28-10 (Date)
by: Steve VanGieson (KCC District Agent's Name)
Plugging Commenced: 6-28-10
Plugging Completed: 6-29-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	219'	none
		Production	4 1/2"	2638'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

A free-point test found the 2 3/8" tubing was stuck at 2100'. LogTech cut the tubing at 2052'. Consolidated spotted 32 sacks of cement (class A with 3% CaCl) down the 4 1/2" casing from 2050' to 1960'. The next day LogTech shot two holes in 4 1/2" casing at 250'. Consolidated pumped 105 sacks of cement down the casing and back up the annulus to surface to plug the well. Cement held level at surface and a metal cap was welded on 8 5/8" casing.

Plugging Contractor License #: 5870 Name: Phillips Well Service
Address 1: P.O. Box 1263 Address 2: _____
City: EIDorado State: KS Zip: 67042 + _____
Phone: (316) 265-6231
Name of Party Responsible for Plugging Fees: Range Oil Company, Inc.
State of Kansas County, Sedgwick, ss.
John M. Washburn Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: John M. Washburn

Box 884, Chanute, KS 66720
431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY																
6-28-10	6942	Walters # B-16	16	24S	SE	Butler																
CUSTOMER Range Oil Co Inc			<table border="1"> <thead> <tr> <th>TRUCK #</th> <th>DRIVER</th> <th>TRUCK #</th> <th>DRIVER</th> </tr> </thead> <tbody> <tr> <td>446</td> <td>Jacob</td> <td></td> <td></td> </tr> <tr> <td>442</td> <td>Eric</td> <td></td> <td></td> </tr> <tr> <td>434</td> <td>Kevin</td> <td></td> <td></td> </tr> </tbody> </table>				TRUCK #	DRIVER	TRUCK #	DRIVER	446	Jacob			442	Eric			434	Kevin		
TRUCK #	DRIVER	TRUCK #					DRIVER															
446	Jacob																					
442	Eric																					
434	Kevin																					
MAILING ADDRESS 125 N. Market. Suite 1120																						
CITY Wichita		STATE Ks	ZIP CODE 67202																			

JOB TYPE Plug HOLE SIZE _____ HOLE DEPTH _____ CASING SIZE & WEIGHT 4 1/2"
 CASING DEPTH _____ DRILL PIPE _____ TUBING 2 3/8" OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
 DISPLACEMENT _____ DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Safety Meeting Rig up to 2 3/8" Tubing Pump 32 sks Class A 3% CC + 25 lbs Poly-Flake and disp cement to 2050ft. Pulled tubing & ran wire line to 1960ft. Wash up & rig down.

RECEIVED

JUL 13 2010

KCC WICHITA

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE	900.00	900.00
5406	15	MILEAGE	3.55	53.25
11045	32 sks	class A	13.10	419.20
1102	100 lbs	Calcium Chloride	.73	72.00
1107	25 lbs	Poly-Flake	2.00	50.00
5502c	2	80 BBL ltr.	96.00	192.00
5409	1	min. bulk del	305.00	305.00
		<u>Subtotal</u>		1992.45
			SALES TAX	30.10
			ESTIMATED TOTAL	2022.55

AVIN 3737
AUTHORIZATION Tire Phillips TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.

Box 884, Chanute, KS 66720
20-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
6-29-10	6942	Walters # B-16	16	245	SE	Butler
CUSTOMER Range Oil Co Inc						
MAILING ADDRESS 125 N. Market, Suite 1120						
CITY Wichita		STATE Ks	ZIP CODE 67202			
			TRUCK #	DRIVER	TRUCK #	DRIVER
			446	Jacob		
			491	Kevin		
			434	Eric		

JOB TYPE Plug 0 HOLE SIZE _____ HOLE DEPTH _____ CASING SIZE & WEIGHT 4 1/2"
CASING DEPTH _____ DRILL PIPE _____ TUBING 2 3/8 OTHER _____
SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
DISPLACEMENT _____ DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Safety Meeting Rig up to 4 1/2" casing Pump 105 sks 60/40p02 4% gel & circulated to surface, Perfs at 250 ft. Washup rig down.

RECEIVED

JUL 13 2010

KCC WICHITA

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405A	1	PUMP CHARGE	605.00	605.00
5406	15	MILEAGE	3.55	53.25
1131	105	60/40p02	11.00	1155.00
1118A	420 lbs	gel	.20	84.00
5502C		80 BBL Vactruck	96.00	288.00
5407	1	min. Bulk Del.	305.00	305.00
		Subtotal		2490.25
		SALES TAX		68.16
		ESTIMATED TOTAL		2558.41

Ravin 3737

235065

AUTHORIZATION Tirel Phillips TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.