

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

RECEIVED ORIGINAL

Form ACO-1

June 2009

Form Must Be Typed

Form must be Signed

All blanks must be Filled

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE KCC WICHITA

OPERATOR: License # 32948
Name: Tomlinson Operating, LLC
Address 1: 7154 W State St. PMB 302
Address 2: _____
City: Boise State: ID Zip: 83714 + _____
Contact Person: Sid Tomlinson
Phone: (208) 229-1937
CONTRACTOR: License # 33350
Name: Southwind Drilling, Inc.
Wellsite Geologist: Robert Milford
Purchaser: NCRA

Designate Type of Completion:

- New Well Re-Entry Workover
- Oil WSW SWD SIOW
 Gas D&A ENHR SIGW
 OG GSW Temp. Abd.
 CM (Coal Bed Methane)
 Cathodic Other (Core, Expl., etc.): _____

If Workover/Re-entry: Old Well Info as follows:

Operator: _____
Well Name: _____

Original Comp. Date: _____ Original Total Depth: _____

- Deepening Re-perf. Conv. to ENHR Conv. to SWD
 Conv. to GSW
- Plug Back: _____ Plug Back Total Depth _____
 Commingled Permit #: _____
 Dual Completion Permit #: _____
 SWD Permit #: _____
 ENHR Permit #: _____
 GSW Permit #: _____

<u>6-18-2010</u>	<u>6-27-10</u>	<u>8-03-2010</u>
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 163-23872 - 0000

Spot Description: _____

SW SE NW SW Sec. 32 Twp. 10 S. R. 20 East West

1,600 Feet from North / South Line of Section

750 Feet from East / West Line of Section

Footages Calculated from Nearest Outside Section Corner:

NE NW SE SW

County: Rooks

Lease Name: Keller B Well #: 1

Field Name: Trico

Producing Formation: Arbuckle

Elevation: Ground: 2114 Kelly Bushing: 2123

Total Depth: 3800 Plug Back Total Depth: 3750

Amount of Surface Pipe Set and Cemented at: 324 Feet

Multiple Stage Cementing Collar Used? Yes No

If yes, show depth set: 1583 Feet

If Alternate II completion, cement circulated from: 1583

feet depth to: surface w/ 225 sx cmt.

Drilling Fluid Management Plan

(Data must be collected from the Reserve Pit)

Chloride content: 68,000 ppm Fluid volume: 400 bbls

Dewatering method used: evaporation

Location of fluid disposal if hauled offsite: _____

Operator Name: _____

Lease Name: _____ License #: _____

Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West

County: _____ Permit #: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

AFFIDAVIT

I am the affiant and I hereby certify that all requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Sid Tomlinson

Title: Member Date: 9/21/2010

KCC Office Use ONLY

Letter of Confidentiality Received
Date: _____

Confidential Release Date: _____

Wireline Log Received

Geologist Report Received

UIC Distribution

ALT I II III Approved by: Dg Date: 9/27/10

Operator Name: Tomlinson Operating, LLC Lease Name: Keller B Well #: 1
 Sec. 32 Twp. 10 S. R. 20 East West County: Rooks

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach complete copy of all Electric Wire-line Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Attach Additional Sheets)</i> Samples Sent to Geological Survey <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Electric Log Submitted Electronically <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <i>(If no, Submit Copy)</i> List All E. Logs Run: Log-Tech: Dual Induction, dual compensated porosity, and microresistivity log.	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample <table style="width:100%; border-collapse: collapse;"> <thead> <tr> <th style="text-align: left;">Name</th> <th style="text-align: left;">Top</th> <th style="text-align: left;">Datum</th> </tr> </thead> <tbody> <tr> <td>Anhydrite</td> <td>1575</td> <td>+548</td> </tr> <tr> <td>Topeka</td> <td>3154</td> <td>-1031</td> </tr> <tr> <td>Heebner</td> <td>3356</td> <td>-1233</td> </tr> <tr> <td>Lansing</td> <td>3396</td> <td>-1273</td> </tr> <tr> <td>Base Kansas City</td> <td>3617</td> <td>-1494</td> </tr> <tr> <td>Arbuckle</td> <td>3686</td> <td>-1563</td> </tr> <tr> <td>TD</td> <td>3795</td> <td>-1672</td> </tr> </tbody> </table>	Name	Top	Datum	Anhydrite	1575	+548	Topeka	3154	-1031	Heebner	3356	-1233	Lansing	3396	-1273	Base Kansas City	3617	-1494	Arbuckle	3686	-1563	TD	3795	-1672
Name	Top	Datum																							
Anhydrite	1575	+548																							
Topeka	3154	-1031																							
Heebner	3356	-1233																							
Lansing	3396	-1273																							
Base Kansas City	3617	-1494																							
Arbuckle	3686	-1563																							
TD	3795	-1672																							

CASING RECORD <input type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12 1/4	8 5/8	23	324	common	225	2%gel, 3% CaCl
Production	7 7/8	5 1/2	15.50	3794	common	150	10% salt

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	# Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input checked="" type="checkbox"/> Plug Off Zone	3686-3706	common	60	

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	3690-3696	350 gals 15% acid	3690-96
		RECEIVED	
		SEP 24 2010	
		KCC WICHITA	

TUBING RECORD:	Size: <u>2 7/8</u>	Set At: <u>3747</u>	Packer At:	Liner Run: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Date of First, Resumed Production, SWD or ENHR. <u>8-04-2010</u>		Producing Method: <input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain) _____		
Estimated Production Per 24 Hours	Oil Bbls. <u>20</u>	Gas Mcf	Water Bbls. <u>0</u>	Gas-Oil Ratio <u>32</u>

DISPOSITION OF GAS: <input type="checkbox"/> Vented <input type="checkbox"/> Sold <input type="checkbox"/> Used on Lease <i>(If vented, Submit ACO-18.)</i>	METHOD OF COMPLETION: <input type="checkbox"/> Open Hole <input checked="" type="checkbox"/> Perf. <input type="checkbox"/> Dually Comp. <input type="checkbox"/> Commingled <i>(Submit ACO-5)</i> <i>(Submit ACO-4)</i> <input type="checkbox"/> Other (Specify) _____	PRODUCTION INTERVAL: <u>3690-3696</u>
---	--	--

Tomlinson Operating, LLC
7154 W. State Street, PMB 302
Boise, ID 83714

SID TOMLINSON
CYNDA TOMLINSON
208-229-1937
tomlinson.operating@gmail.com

KELLER 'B' #1

S/2 NW SW (1600' FSL & 750' FWL)
Sec. 32-10-20W, Rooks Co., Kansas
API #15-163-23872-00-00

Elevations: KB 2123 ' Ground 2114'

6-17-10 Moving in & rigging up Southwind rig #2.

6-18 TD 325'. Preparing to run surface casing. Spud 7:40 AM today.

6-19 TD 1298', pulling plugged bit. **Ran 11 jts. (315') new 8 5/8", 23# casing and set 1' off bottom at 324'. Quality cemented with 225 sacks common + 2% gel + 3% CaCl.** Plug down 1:30 PM on 18th. **Cement circulated to surface.** Waited 8 hours for cement to set.

6-20 Drilling at 2155'. Anhydrite 1579'-1626'. **Anhydrite top (+544).**

6-21 Drilling at 2730'.

6-22 TD 3194. Making short trip for DST #1.

6-23 Drilling at 3410'. Ran DST #1, Topeka 30' zone.

6-24 TD 3570', circulating for samples. Ran DST #2 Lansing E/F zones.

6-25 TD 3625'. going in hole to drill after DST #4.

6-26 TD 3715, preparing to run DST #6.

6-27 TD 3800'. Laying down drill pipe to run 5 2" casing.

6-28-10 Waiting on cement. **Ran 85 jts. (3783') new 5 1/2", 15.5#, API J-55 casing and set at 3794'. Port collar @ 1583'. Quality cemented with 150 sacks common + 10% salt.** Ran 500 gallons Mud Flush ahead of cement. Job complete 12:30 PM on 27th.

Deviation surveys: 1 degree @325', 1 degree @ 1298', 1 1/4 degree @ 3194', 3/4 degree @ 3800'.

Drill Stem Tests:

6-22-10 **DST #1 3175-3194 (Topeka 30' zone).** 30/30/30/30

Recovered 10' oil spotted mud.

IFP 15-19 FFP 20-21 **SIP 756-703 psi**

6-23-10 **DST #2 3468-3492 (Lansing E/F zones)** 30/45/60/60

Recovered 200' total fluid: **50' slightly gassy oil (38 gravity)** and 30' slightly water cut mud(95% mud), and 120' slightly mud cut water(85% water, 95,000 PPM chlorides). IFP 24-54 FFP 60-109 SIP 709-702 psi

6-24-10 **DST #3 3520-3570 (Lansing H/I zones)** 30/30/30/30

Recovered 10' sli oil and water cut mud(90% mud).

IFP 18-24 FFP 12-20 SIP 106-77 psi.

6-25-10 **DST #4 3566-3625 (Lansing J/K zones).** 30/30/30/30

Recovered 15' sli oil cut mud (90% mud).

IFP 18-20 FFP 20-22 SIP 159-56 PSI

DST #5 3618-3699 (6' into Arbuckle) 30/45/60/60

Recovered 150' total fluid : **75' free oil (39 gravity) + 75' mud cut oil.**

IFP 22-45 FFP 46-80 **SIP 1046 -1005**

6-26-10 **DST #6 3699-3715 (22' into Arbuckle)** 30/45/60/60

Recovered 90' gas in pipe & 580' total fluid: **520' gassy oil (36 gravity) & 60' gassy mud cut oil (50% oil).**

IFP 26-101 FFP 107-238 **SIP 1157-1139 psi.**

RECEIVED

SEP 24 2010

KCC WICHITA

QUALITY OILWELL CEMENTING, INC.

Phone 785-483-2025
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 4007

Date	7-9-10	Sec.	Twp.	Range	County	State	On Location	Finish
Lease	Keller "B"	Well No.	2	Location	Ellis N to CL W to 1 st Curve 1/4 N E 1/4			10:31 AM
Contractor	Express Well	Owner	To Quality Oilwell Cementing, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.					
Type Job	Port Collar	Hole Size	T.D.	Charge To	Sid Tomlinson Operating LLC			
Csg.	5 1/2	Depth		Street				
Tbg. Size	2 1/2	Depth		City	State			
Tool		Depth		The above was done to satisfaction and supervision of owner agent or contractor.				
Cement Left in Csg.		Shoe Joint		Cement Amount Ordered	400 40 6 1/2 gel 1/4 lb Flo Seal			
Meas Line		Displace	8 1/4 bbls	EQUIPMENT				
				Used	230			
Pumptrk	5	No.	Cementer	Brandon	Common	138		
			Helper					
Bulktrk	12	No.	Driver	Rocky	Poz. Mix	92		
			Driver					
Bulktrk	PU	No.	Driver	DAVE	Gel.	12		
			Driver					
JOB SERVICES & REMARKS				Calcium				
Remarks:				Hulls				
Rat Hole				Salt				
Mouse Hole				Flowseal	100#			
Centralizers				Kol-Seal				
Baskets				Mud CLR 48				
D/V or Port Collar	@ 1583'			CFL-117 or CD110 CAF 38				
				Sand				
	pressured casing @ 2800 PSI			Handling	417			
	+ Neld. opened tool purged			Mileage	33			
	and got cir. mixed 230			FLOAT EQUIPMENT				
	IK + cir. cement to surface			Guide Shoe				
				Centralizer				
				Baskets				
	Closed tool checked @ 2800 PSI			AFU Inserts				
	+ Neld. ran 5 TB & wash			Float Shoe				
	CLEAN.			Latch Down				
	Thanks			Pumptrk Charge	port collar			
				Mileage	33			
				RECEIVED				
				SEP 24 2010				
				KCC WICHITA				
				Tax				
				Discount				
				Total Charge				
X Signature	Terry A. Piesher							

QUALITY OILWELL CEMENTING, INC.

Phone 785-483-2025
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 4104

Date	Sec.	Twp.	Range	County	State	On Location	Finish
6-27-10	32	10	20	Rooks	Kansas		12:30 PM
Lease Keller	Well No. B-1		Location Ellis N. to Co. Line 260 3N F 1st				
Contractor Sandwind Drilling Rig				Owner			
Type Job Production String				To Quality Oilwell Cementing, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.			
Hole Size 7 7/8	T.D. 3800		Charge To Tomlinson Operating				
Csg. 5 1/2 15.50lb	Depth 3797		Street				
Tbg. Size	Depth		City State				
Tool Port Collar	Depth 1583		The above was done to satisfaction and supervision of owner agent or contractor.				
Cement Left in Csg. 40'	Shoe Joint 40'		Cement Amount Ordered 200 Cem 10% Salt				
Meas Line	Displace 89 1/2 Bbl		500 bbl Mud Clear -48				
EQUIPMENT				Common 200			
Pumptrk 5 No. Cementer	Helper Steve		Poz. Mix				
Bulktrk 8 No. Driver	Brandon		Gel.				
Bulktrk No. Driver	C150		Calcium				
JOB SERVICES & REMARKS				Production casing			
Remarks:				Hulls			
Rat Hole 30sx				Salt 22			
Mouse Hole 20sx				Flowseal			
Centralizers 1, 3, 5, 13, 14, & 49				Kol-Seal			
Baskets 50				Mud CLR 48 500 gal			
D/V or Port Collar				CFL-117 or CD110 CAF 38			
30 sx Rat Hole				Sand			
20 sx Mouse Hole				Handling 222			
Land plug @ 1200psi				Mileage			
Float Held				FLOAT EQUIPMENT			
				Guide Shoe			
				Centralizer 6			
				Baskets 1			
				AFU Inserts			
				Float Shoe 1			
				Latch Down 1			
				1 Port Collar			
				Pumptrk Charge prod long string			
				Mileage 33			
				Tax			
				Discount			
				Total Charge			
Signature Terry W. Precher							

RECEIVED
SEP 24 2010
KCC WICHITA

Quality Oilwell
Cementing

DEFINITIONS: In these terms and conditions, "Quality" shall mean Quality Oilwell Cementing, Inc., and "Customer" shall refer to the party identified by that term on the front of this contract. As applicable, "Job" relates to the services described on the front side of this contract, "merchandise" refers to the material described on the front of this contract and to any other materials, products, or supplies used, sold, or furnished under the requirements of this contract.

- **TERMS:** Unless satisfactory credit has been established, "CUSTOMER" must tender full cash payment to "QUALITY" before the job is undertaken or merchandise is delivered. If satisfactory credit has been established, the terms of payment for the job and/or merchandise, including bulk cement, are net cash, payable in 30 days from the completion of the job and/or delivery of the merchandise. For all past due invoices, "CUSTOMER" agrees to pay interest on amounts invoiced at a rate of 18 percent per annum until paid. Notwithstanding the foregoing in no event shall this Contract provide for interest exceeding the maximum rate of interest that "CUSTOMER" may agree to pay under applicable law. If any such interest should be provided for, it shall be and hereby is deemed to be a mistake, and this contract shall be automatically reformed to lower the rate of interest to the maximum legal contract rate, any amounts previously paid as excess interest shall be deducted from the amounts owing from the "CUSTOMER" or at the option of "QUALITY" refunded directly to "CUSTOMER." For purposes of this paragraph, QUALITY and CUSTOMER agree that KANSAS law shall apply. Any discounts granted with this contract are null and void if the charges are not paid when due.

- **ATTORNEY FEES:** In any legal action or proceeding between the parties to enforce any of the terms of this Service Contract, or in any way pertaining to the term of this Contract, the prevailing party shall be entitled to recover all expenses, including, but not limit to, a reasonable sum as and attorney's fees.

- **PRICES AND TAXES:** All merchandise listed in "QUALITY'S" current price schedule are F.O.B. QUALITY'S local station and are subject to change without notice. All prices are exclusive of any federal, state, local, or special taxes for the sale or use of the merchandise or services listed. The amount of taxes required to be paid by QUALITY shall be added to the quoted prices charged to CUSTOMER.

- **TOWING CHARGES:** QUALITY will make a reasonable attempt to get to and from each job site using its own equipment. Should QUALITY be unable to do so because of poor or inadequate road conditions, and should it become necessary to employ a tractor or other pulling equipment to get to or from the job site, the tractor or pulling equipment will be supplied by CUSTOMER or, if furnished by QUALITY, will be charged to and paid by CUSTOMER.

- **PREPARATION CHARGES:** If a job and/or merchandise is ordered and CUSTOMER cancels the order after preparation of a chemical solution or other material, CUSTOMER will pay QUALITY for the expenses incurred by QUALITY as a result of the cancellation.

- **DEADHAUL CHARGES:** Unless otherwise specified on the front of this Contract, a deadhaul charges as set forth in QUALITY'S current price book will be charged each way for each service unit which is ordered by CUSTOMER but not used.

- **SERVICE CONDITIONS AND LIABILITIES:** 1. QUALITY carries public liability and property damage insurance, but since there are so many uncertain and unknown conditions beyond QUALITY'S control, QUALITY shall not be liable for injuries to property or persons or for loss or damage arising from the performance of the job or delivery of the merchandise. Customer shall be responsible for and indemnify, defend, and hold harmless QUALITY, its officers, agents and employees, from and against any and all claims or suits for:

(A) Damage to property or for bodily injury, sickness, disease, or death, brought by any person, including CUSTOMER and/or the well owner, and

(B) Oil spills, pollution, surface or sub-surface damage, injury to the well, reservoir loss, or damage arising from a well blowout arising out of or in connection with QUALITY'S performance of the job or furnishing of merchandise in accordance with this contract, unless such loss or damage is caused by the willful misconduct or gross negligence of QUALITY or its employees.

2. With respect to any of QUALITY'S tools, equipment, or instruments which are lost in the well or damaged when performing or attempting to perform the job or, in the case of marine operations, are lost or damaged at any time after delivery to the landing for CUSTOMER and before return to QUALITY at the landing, CUSTOMER shall either recover the lost item without cost to QUALITY or reimburse QUALITY the current replacement cost of the item unless the loss or damage results from the sole negligence of QUALITY or its employees.

3. QUALITY does not assume any liability or responsibility for damages or conditions resulting from chemical action in cements caused by contamination of water or other fluids.

WARRANTIES: 1. QUALITY warrants all merchandise manufactured or furnished by it to be free from defects in material and workmanship under normal use and service when installed, and used, and/or serviced in the manner provided and intended. QUALITY'S obligation under this warranty is expressly limited to repair replacement, or allowance for credit, at its option, for any merchandise which is determined by QUALITY to be defective. THIS IS THE SOLE WARRANTY OF QUALITY AND NO OTHER WARRANTY IS APPLICABLE, EITHER EXPRESS OR OTHERWISE IMPLIED, IN FACT OR IN LAW, INCLUDING ANY WARRANTY AS TO MERCHANTABILITY OR FITNESS FOR A PARTICULAR USE OR PURPOSE. CUSTOMER'S sole and only remedy with regard to any defective merchandise shall be the repair or replacement thereof or allowance for credit as herein provided, and QUALITY shall not be liable for any consequential, special, incidental, or punitive damages resulting from or caused by defective materials, products or supplies.

2. More specifically:

(A) Nothing in this contract shall be construed as a warranty by QUALITY of the success or the effectiveness of the result of any work done or merchandise used, sold, or furnished under this contract.

(B) Nothing in this contract shall be construed as a warranty of the accuracy or correctness of any facts, information, or data furnished by QUALITY or any interpretation of test, meter readings, chart information, analysis or research, or recommendations made by QUALITY, unless the inaccuracy or incorrectness is caused by the willful misconduct or gross negligence of QUALITY or its employees in the preparation or furnishing of such facts, information or data. (C) Work done by QUALITY shall be under the direct supervision and control of the CUSTOMER or his agent and QUALITY will accomplish the job as an independent contractor and not as an employee or agent of the CUSTOMER.

QUALITY OILWELL CEMENTING, INC.

Phone 785-483-2025
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 4045

Date	6-18-10	Sec.	32	Twp.	10	Range	20	County	Reels	State	Kansas	On Location		Finish	1:30pm	
Lease	Roddy	Well No.	B-1			Location						Ellis N. tele. line 2W 1/2 N Emb				
Contractor	Sutherland Drilling Rig?							Owner								
Type Job	Surface							To Quality Oilwell Cementing, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.								
Hole Size	12 1/4		T.D.		325		Charge To								Sid Tomlinson	
Csg.	8 3/8 23 1/2		Depth		325		Street								7134 W State St PMB 302	
Tbg. Size			Depth				City								Boise State Id 83714	
Tool			Depth				The above was done to satisfaction and supervision of owner agent or contractor.									
Cement Left in Csg.	10-15		Shoe Joint				Cement Amount Ordered								225 Com 30 PCC	
Meas Line			Displace		19 3/4 Bbl											

EQUIPMENT

Pumptrk	9	No.	Cementer	Steve	4	Common	225
Bulktrk	8	No.	Helper	Steve	3	Poz. Mix	
Bulktrk		No.	Driver	Dave	3	Gel.	4
		No.	Driver	150	2	Calcium	7

JOB SERVICES & REMARKS

Remarks:	Hulls
Rat Hole	Salt
Mouse Hole	Flowseal
Centralizers	Kol-Seal
Baskets	Mud CLR 48
D/V or Port Collar	CFL-117 or CD110 CAF 38
	Sand
	Handling 236
	Mileage 33

Cement did Circulate


FLOAT EQUIPMENT

Guide Shoe	
Centralizer	RECEIVED
Baskets	SEP 24 2010
AFU Inserts	
Float Shoe	KCC WICHITA
Latch Down	

Thank You

SURFACE

Pumptrk Charge	Surface	Tax	
Mileage	33	Discount	
Hours	(Russell)	Total Charge	
Signature	<i>William Anderson</i>		



DEFINITIONS: In these terms and conditions, "Quality" shall mean Quality Oilwell Cementing, Inc., and "Customer" shall refer to the party identified by that term on the front of this contract. As applicable, "Job" relates to the services described on the front side of this contract, "merchandise" refers to the material described on the front of this contract and to any other materials, products, or supplies used, sold, or furnished under the requirements of this contract.

- **TERMS:** Unless satisfactory credit has been established, "CUSTOMER" must tender full cash payment to "QUALITY" before the job is undertaken or merchandise is delivered. If satisfactory credit has been established, the terms of payment for the job and/or merchandise, including bulk cement, are net cash, payable in 30 days from the completion of the job and/or delivery of the merchandise. For all past due invoices, "CUSTOMER" agrees to pay interest on amounts invoiced at a rate of 18 percent per annum until paid. Notwithstanding the foregoing in no event shall this Contract provide for interest exceeding the maximum rate of interest that "CUSTOMER" may agree to pay under applicable law. If any such interest should be provided for, it shall be and hereby is deemed to be a mistake, and this contract shall be automatically reformed to lower the rate of interest to the maximum legal contract rate, any amounts previously paid as excess interest shall be deducted from the amounts owing from the "CUSTOMER" or at the option of "QUALITY," refunded directly to "CUSTOMER." For purposes of this paragraph, QUALITY and CUSTOMER agree that KANSAS law shall apply. Any discounts granted with this contract are null and void if the charges are not paid when due.

- **ATTORNEY FEES:** In any legal action or proceeding between the parties to enforce any of the terms of this Service Contract, or in any way pertaining to the term of this Contract, the prevailing party shall be entitled to recover all expenses, including, but not limit to, a reasonable sum as and attorney's fees.

- **PRICES AND TAXES:** All merchandise listed in "QUALITY'S" current price shall schedule are F.O.B. QUALITY'S local station and are subject to change without notice. All prices are exclusive of any federal, state, local, or special taxes for the sale or use of the merchandise or services listed. The amount of taxes required to be paid by QUALITY shall be added to the quoted prices charged to CUSTOMER.

- **TOWING CHARGES:** QUALITY will make a reasonable attempt to get to and from each job site using its own equipment. Should QUALITY be unable to do so because of poor or inadequate road conditions, and should it become necessary to employ a tractor or other pulling equipment to get to or from the job site, the tractor or pulling equipment will be supplied by CUSTOMER or, if furnished by QUALITY, will be charged to and paid by CUSTOMER.

- **PREPARATION CHARGES:** If a job and/or merchandise is ordered and CUSTOMER cancels the order after preparation of a chemical solution or other material, CUSTOMER will pay QUALITY for the expenses incurred by QUALITY as a result of the cancellation.

- **DEADHAUL, CHARGES:** Unless otherwise specified on the front of this Contract, a deadhaul charges as set forth in QUALITY'S current price book will be charged each way for each service unit which is ordered by CUSTOMER but not used.

- **SERVICE CONDITIONS AND LIABILITIES:** 1. QUALITY carries public liability and property damage insurance, but since there are so many uncertain and unknown conditions beyond QUALITY'S control, QUALITY shall not be liable for injuries to property or persons or for loss or damage arising from the performance of the job or delivery of the merchandise. Customer shall be responsible for and indemnify, defend, and hold harmless QUALITY, its officers, agents and employees, from and against any and all claims or suits for:

(A) Damage to property or for bodily injury, sickness, disease, or death, brought by any person, including CUSTOMER and/or the well owner; and:

(B) Oil spills, pollution, surface or sub-surface damage, injury to the well, reservoir loss, or damage arising from a well blowout arising out of or in connection with QUALITY'S performance of the job or furnishing of merchandise in accordance with this contract, unless such loss or damage is caused by the willful misconduct or gross negligence of QUALITY or its employees.

2. With respect to any of QUALITY'S tools, equipment, or instruments which are lost in the well or damaged when performing or attempting to perform the job or, in the case of marine operations, are lost or damaged at any time after delivery to the landing for CUSTOMER and before return to QUALITY at the landing, CUSTOMER shall either recover the lost item without cost to QUALITY or reimburse QUALITY the current replacement cost of the item unless the loss or damage results from the sole negligence of QUALITY or its employees.

3. QUALITY does not assume any liability or responsibility for damages or conditions resulting from chemical action in cements caused by contamination of water or other fluids.

WARRANTIES: 1. QUALITY warrants all merchandise manufactured or furnished by it to be free from defects in material and workmanship under normal use and service when installed, and used, and/or serviced in the manner provided and intended. QUALITY'S obligation under this warranty is expressly limited to repair replacement, or allowance for credit, at its option, for any merchandise which is determined by QUALITY to be defective. THIS IS THE SOLE WARRANTY OF QUALITY AND NO OTHER WARRANTY IS APPLICABLE, EITHER EXPRESS OR OTHERWISE IMPLIED, IN FACT OR IN LAW, INCLUDING ANY WARRANTY AS TO MERCHANTABILITY OR FITNESS FOR A PARTICULAR USE OR PURPOSE, CUSTOMER'S sole and only remedy with regard to any defective merchandise shall be the repair or replacement thereof or allowance for credit as herein provided, and QUALITY shall not be liable for any consequential, special, incidental, or punitive damages resulting from or caused by defective materials, products or supplies.

2. More specifically:

(A) Nothing in this contract shall be constructed as a warranty by QUALITY of the success or the effectiveness of the result of any work done or merchandise used, sold, or furnished under this contract.

(B) Nothing in this contract shall be construed as a warranty of the accuracy or correctness of any facts, information, or data furnished by QUALITY or any interpretation of test, meter readings, chart information, analysis or research, or recommendations made by QUALITY, unless the inaccuracy or incorrectness is caused by the willful misconduct or gross negligence of QUALITY or its employees in the preparation or furnishing of such facts, information or data. (C) Work done by QUALITY shall be under the direct supervision and control of the CUSTOMER or his agent and QUALITY will accomplish the job as an independent contractor and not as an employee or agent of the CUSTOMER.