

WELL PLUGGING RECORD
OR
FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission,
800 Bittling Building
Wichita, Kansas

Trego County. Sec. 17 Twp. 13S Rge. (E) 21 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines 40' 2" S. Wagg #1, which was
Lease Owner Central Com'l Co. located NWC NW SE

Lease Name John Wagg Well No. 1A

Office Address 517 Central Bank Bldg., Tulsa, Okla.

Character of Well (Completed as Oil, Gas or Dry Hole) Oil

Date, well completed August 4, 1936 193

Application for plugging filed Sept. 5, 1940 193

Application for plugging approved Sept. 5, 1940 193

Plugging Commenced Oct, 5, 1940 193

Plugging Completed Oct, 9, 1940. 193

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 193

Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Yes

Name of Conservation Agent who supervised plugging of this well C. T. Alexander

Producing formation Lime Sandy Depth to top 3874 Bottom 3900 Total Depth of Well 3900 Feet

Show depth and thickness of all water, oil and gas formations. from 4563'


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Lime, Show of oil		3613	3621	20"	36'	
" " " " & Gas		3643	3650	15 1/2"	565' 5"	All
Lime, Oil show		3874	3881	12 1/2"	1364' 3"	"
Lime Oil		3881	3885	10"	1622' 2"	"
Lime Oil		3885	3908	8 5/8"	2782' 10"	"
				6 5/8"	2752' 11"	"
				5 3/16"	3865'	1008' 3"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Casing Puller advises plugged in compliance and in accordance with instructions of C. T. Alexander.



11-07-40

(If additional description is necessary use BACK of this sheet)

Correspondence regarding this well should be addressed to Central Commercial Company,
Address 517 Central Bank Bldg., P.O. Box 2306, Tulsa, Oklahoma.

STATE OF Oklahoma, COUNTY OF Tulsa, ss.

L. J. Zoller (employee of owner) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

517 Central Bank Bldg., Tulsa, Oklahoma.


(Address)

SUBSCRIBED AND SWORN to before me this 25th day of October, 1940.

My commission expires April 3, 1941.

[Signature]

Notary Public.



CENTRAL COMMERCIAL OIL COMPANY

JOHN WAGG No. 1A.

Located 40'2" South of Waggs #1,
which was located NWc NW SE of
Section 17-13S-21W, Trego County,
Kansas.

D E E P E N I N G R E C O R D

Commenced: April 14, 1936.

Completed July 10, 1936.

FROM	TO	FORMATION	FROM	TO	FORMATION	
3908	3918	Lime & shale blue	4552	4557	Granite wash Sandy	
3918	3925	Lime & shale broken	4557	4562	Granite Wash	
3925	3935	Lime	4562	4563	Granite (solid)	
3935	3940	Lime				
3940	3947	Lime & shale broken			<u>PLUGGED BACK</u>	
3947	3966	Lime Broken				
3966	3988	Lime	Commenced	7-18-36		
3988	3990	Sandy Lime	Comp.	8- 4-36		
3990	4003	Lime Gray hard				
4003	4005	Sand			5 3/16" pipe set at 3865'	
4005	4009	Lime Gray & Hard			Bottom of hole 3900'.	
4009	4029	Sand			Production approx. 8 bbls. a day.	
4029	4041	Lime Gray				
4041	4050	Sand Hard				
4050	4060	Lime Gray & Brown				
4060	4067	Lime White			<u>CASING RECORD:</u>	
4067	4077	Lime Sandy	20"	90#	36'	Pulled
4077	4139	Lime Sandy	15 1/4"	70#	565'5"	All
4139	4151	Lime	12 1/2"	50#	1364'3"	"
4151	4160	Lime Sandy	10"	45#	1622'2"	"
4160	4165	Lime Hard & Fine	8 5/8"	32#	2782'10"	"
4165	4181	Lime Sandy	6 5/8"	24#	2752'11"	"
4181	4189	Lime white	5 3/16"	20#	3865'	1008'3"
4189	4191	Sand Brown				
4191	4237	Lime				
4237	4246	Lime Gray				
4246	4253	Lime Sandy mixed with little shale				
4253	4311	Lime white				
4311	4324	Lime Brown, Green shale showed up in sample				
4324	4372	Lime				
4372	4454	Sand				
4454	4471	Sand with Red Lime				
4471	4473	Sand				
4473	4478	R. R. little Blue Sh.				
4478	4486	Lime Red				
4486	4498	Lime, R. R. falling in.				
4498	4500	Lime Red & little gray				
4500	4505	Lime Gray & little red				
4505	4522	Lime Hard				
4522	4525	Sand Conglomerate				
4525	4531	Sand & Lime Conglomerate				
4531	4536	Sand & Granite mixed				
4536	4543	Granite wash				
4543	4552	Sand & Lime				

17 13 21W
115 19

NO. 7
STATE OF KANSAS
COMMISSIONER