


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Trego County, Sec. 17 Twp. 13 Rge. 21 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

Lease Owner Fickerell Drilling Company
Lease Name Wagg # 471 Well No. _____
Office Address Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 7/6/76 _____ 19____
Plugging completed 7/8/76 _____ 19____
Reason for abandonment of well or producing formation
depleted.
If a producing well is abandoned, date of last production
_____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4010
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	FOOT IN	PULLED OUT
				8-5/8	217	none
				4 1/2"	3750	2619'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Sanded back to 3550' and ran 3 sacks cement. Loaded hole, shot pipe at
2722', 2606', pulled 66 joints. Plugged well with 3 sacks hulls, 130
sacks cement, 50-50 pos, 6% gel.

PLUGGING COMPLIANCE

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KYSO CASING PULLING
CHASE, KANSAS


STATE OF KANSAS COUNTY OF RICE
R. DANIEL KANSO (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Daniel KANSO
CHASE, KANSAS

SUBSCRIBED AND SWORN TO before me this 15th day of July 1976

Margaret Melcher
Notary Public

My commission expires



07-19-76

WELL INFORMATION

WELL: Wagg A-1
 LOC.: NE SE SE Sec. 17-13S-21W
 Trego County, Kansas
 FIELD: RIGA
 T.D.: 4013 (Great Guns) 4010 (Rotary)
 CASING & CEMENT 8 5/8" @ 217' w/150 sx.
 4½" 10.5# Limited Service @ 3750 w/75 sx.
 50-50 Poz w/4% gel plus 75 sx. common
 CEMENT TOP: 3000 ft. (theoretical)
 3150 ft. (estimated based on 80% fillup)
 PBTD: 3572-3576 (Lansing "B")

RECEIVED
 CONSERVATION DIVISION

JUN 30 1976

CONSERVATION DIVISION
 WASHINGTON, D.C.

COMPANY: PICKRELL DRILLING COMPANY
705 4th National Bank Bldg.
Wichita, Kansas
LOCATION: Wagg "A"
NW SE SE 17-13-21W
Trego County, Kansas
CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

Rotary Drilling Commenced 12-10-74
Rotary Drilling Completed 1-22-75

CASING RECORD: 8 5/8 surface casing set at 217 with 150 sacks cement. Job completed 12-10-74 @ 8PM. 4 1/2" set at 3745 with 75 sacks common & 75 sacks Pozmix 4% gel.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

40	Top Soil & Sand
115	Sand & Post Rock
220	Shale
360	Shale
1080	Shale Red Beds
1315	Sand
1400	Shale
1588	Shale
1800	Anhy.
2275	Shale
2420	Lime & Shale
2600	Lime & Shale
2820	Lime & Shale
2925	Lime & Shale
3135	Shale & Lime
3300	Lime & Shale
3360	Lime & Shale
3455	Lime & Shale
3545	Lime & Shale
3585	Lansing
3588	Lansing
3620	Lansing
3655	Lime & Shale
3709	Lime
3765	Lime
3830	Lime
3885	Lime & Shale
3910	Lime
3928	Lime
3943	Chert & Shale
3960	Arbuckle
4010	Lime

Handwritten notes and stamps, including "JUN 30 1975" and "Wichita, Kansas".

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 11 day of March, 1975, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: August 19, 1975

Helen L. Martin
Notary Public
Helen L. Martin