


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 35 Twp. 11S Rge. 16W (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SW SW
Lease Owner Richard G. Smith
Lease Name CHRYSLER #1 Well No. 1
Office Address 1023 Beacon Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D&A
Date well completed 4/23/62 1962
Application for plugging filed April 23 1962
Application for plugging approved April 23 1962
Plugging commenced April 23 1962
Plugging completed April 23 1962
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3492 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	208'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set #1 plug at 420' with 1/4 sack hulls, 20 sacks cement, #2 set at 180, 1/4 sack hulls, 20 sacks cement, #3 set at 40, 1/4 sack hulls, 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
5-28-1962
MAY 28 1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor National Drilling Company, Inc.
Address 531 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Howard A. Stoskopf (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Howard A. Stoskopf
531 Petroleum Building
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of May, 1962

My commission expires September 1, 1965
Cyrilene K. Tegeler
Cyrilene K. Tegeler Notary Public.



15-051-03753-00-00

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPL. BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY RICHARD G SMITH


SEC. 35 T. 11S R. 16W
LOC. SW SW SW

FARM CHRISLER # I NO. I

TOTAL DEPTH 3492'
COMM. 4 16 62 COMP. 4 23 62

COUNTY ELLIS

SHOT OR TREATED
CONTRACTOR NATIONAL DRILLING CO
ISSUED



CASING
20 10
15 8 5/8 208.29' w/135 sks cement
12 6
13 5

ELEVATION
PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

POST ROCK	130
SHALE	207
SHALE	305
SAND	340
SHALE SHELL &	
RED BED	945
RED BED	954
ANHY	992
SHALE OF SHELLS	1470
SHALE & SHELLS	1745
LIME	1920
LIME & SHALE	2100
LIME & SHALE	2240
LIME	2400
SHALE	2660
SHALE & LIME	2815
LIME & SHALE	2880
LIME	3015
LIME	3070
LIME	3160
LIME	3245
LIME & SHALE	3352
CONG	3492
TOTAL DEPTH	3492

I Hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

NATIONAL DRILLING COMPANY INC.

Howard A. Stoskopf
HOWARD A STOSKOPF

STATE OF KANSAS)
SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, in and for said County and State this 23th day of May 1962

Notary Public Cyrilene Tegeler

My Commission Expires: Sept 1 1965