


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ellis County. Sec. 1 Twp. 11 Rge. 17 (E) W (W)  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines SE SE NE NW  
Lease Owner Franco Central Oil Company  
Lease Name Hubbard Well No. 1  
Office Address 750 Fourth Nat'l Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 1, 1960  
Application for plugging filed June 1, 1960  
Application for plugging approved June 1, (verbally) 1960  
Plugging commenced June 1, 1960  
Plugging completed June 1, 1960  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3466 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	202'	8 5/8"	202'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud from total depth to 300 feet with plug and 20 sacks of cement at this point. Filled with mud to 180 feet with a plug and 20 sacks of cement at this point. Filled with mud to 40 feet with a plug and 10 sacks of cement at this point.

RECEIVED  
STATE CORPORATION COMMISSION  
6-16-1960  
JUN 16 1960  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Harms-Burt Drilling Co.  
Address P. O. Box 184, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Allan Harms (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Allan Harms  
P. O. Box 184, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 8 day of June, 1960  
Mary E. Van Pelt  
Notary Public.

My commission expires January 20, 1962



DRILLERS LOG

Company: Franco Central Oil Company  
Farm: Hubbard #1  
Commenced: May 24, 1960  
  
Elevation: 1839 KB

<sup>NW</sup>  
SE SE NE, Section 1-11-17-W  
Ellis County, Kansas  
Completed: June 1, 1960

0 - 202	shale & pyrite
202 - 400	shale & sand streaks
400 - 480	sand
480 - 500	sand (hard)
500 - 745	shale & sand
745 - 1040	red bed & shale
1040 - 1080	anhydrite
1080 - 1350	red bed & shale
1350 - 1600	shale & shells
1600 - 2090	shale & lime
2090 - 2175	lime
2175 - 2790	shale & lime
2790 - 2820	lime & shale
2820 - 3008	lime
3008 - 3014	Heebner shale
3014 - 3060	lime & shale
3060 - 3326	lime
3326 - 3446	conglomerate
3446 - 3466	arbuckle
3466	total depth

RECEIVED  
STATE CORPORATION COMMISSION  
6-16-1960  
JUN 16 1960  
CONSERVATION DIVISION  
Wichita, Kansas

Set 202 feet of 8 5/8" surface pipe. Cemented with 175 sacks of common cement with 2% calcium chloride.

Tops:	Anhydrite	-	1040
	Heebner	-	3008
	Brown Lime	-	3030
	Base KC	-	3289
	Conglomerate	-	3326
	Arbuckle	-	3446

Dry, plugged and abandoned.

STATE OF KANSAS)  
                          ) SS.  
COUNTY OF BARTON)

I, Allan Harms of the Harms-Burt Drilling Company being first duly sworn on oath state:  
I have knowledge of the facts, statements and matters herein contained and the same  
are true and correct.

Subscribed and sworn to before me this 8 day of June, 1960

Allan Harms  
Mary E. Van Pelt  
Notary Public

My commission expires January 20, 1962.