


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 1 Twp. 11S Rge. 17 (E) W (W)
Location as "NE/CNW&SW&" or footage from lines NE NW NE
Lease Owner White Eagle Oil Company
Lease Name Taylor Well No. 1
Office Address First National Building, Tulsa 3, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 17, 19 57
Application for plugging filed July 17, 19 57
Application for plugging approved July 17, 19 57
Plugging commenced July 17, 19 57
Plugging completed July 18, 19 57
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3527 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	251'	8 5/8"	251'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

From 3527' to 800' - heavy rotary mud and plug
800' to 492' - 100 sacks posmix
492' to 240' - heavy rotary mud and plug
240' to 163' - 25 sacks posmix
163' to 40' - heavy rotary mud and plug
40' to 6' - 10 sacks posmix
6' to surface - cellar

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Peel Brothers, Inc.
Address P.O. Box 88, Hoisington, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Peel Brothers, Inc. (employee of owner) or (~~owner/operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. PEEL BROTHERS, INC.
(Signature) BY: Al H. Smith
P.O. Box 88, Hoisington, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of July, 19 57

Ruth Brant
Notary Public.

My commission expires April 27, 1960

PLUGGING
FILE SEC. 1 T. 11 R. 17 W
BOOK PAGE 29 LINE 19

RECEIVED
STATE CORPORATION COMMISSION
7-25-1957
JUL 25 1957
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS' LOG

Company: White Eagle Oil Company
Arm Name: Taylor Well No. 1
Total Depth: 3527'
Comm: 7/7/57 Comp: 7/18/57
Contractor: Peel Brothers, Inc.
Casing: 8 5/8" @ 251'

NE NW NE
Sec. 1, Twp. 11S, Rge. 17W,
County: Ellis,
Kansas
Elevation:
Production: Dry

Figures below indicate bottoms of formations:

Clay	0 -	60
Blue shale		130
Shale and shells		252
Sand and shale		550
Sand and pyrite		600
Sand		775
Redrock and shale		780
Shale and red bed		1115
Anhydrite		1145
Shale and red bed		1660
Shale and shells		1935
Shale and lime		2670
Lime		3394
Cherty Cong.		3522
Lime		3527
Total Depth		3527

This is to certify that the above information is to the best of our knowledge, true and correct.

PEEL BROTHERS, INC.

BY: Al H. Smith

SUBSCRIBED AND SWORN to before me this 19th day of July, 1957

My commission expires: April 27, 1960

Ruth Brant
Notary Public

PLUGGING
FILE SEC. 1 T. 11 S. 17 W.
BOOK PAGE 29 LINE 19

RECORDED
STATE OF KANSAS
JUL 25 1957
COMMISSION EXPIRES
JUL 25 1960