

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE NAME Madsen 1-28
 WELL NUMBER 1-28
 _____ Ft. from S Section Line
 _____ NE NE SE _____ Ft. from E Section Line
 SEC. 28 TWP. 11 RGE. 16 (E) or (W)
 COUNTY Ellis
 Date Well Completed 1960
 Plugging Commenced 7-6-93
 Plugging Completed 7-6-93

LEASE OPERATOR Berexco, Inc.
 ADDRESS Box 723 Hays, Kansas 67601
 PHONE# (913) 628 6101 OPERATORS LICENSE NO. 5363

Character of Well SWD EOR
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-6-93 (date)
 by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3322

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	943	8 5/8		
	Casing	0	3385	4 1/2		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each section. Perf. 2 holes at 1000'. Run tubing to 1000'. Spot 100 sk. common at this depth. Hole circulate Pull tubing to 200'. Mix 50 sk. 60/40 posmix, 10% gel 1/4 FC per sk., 50# hulls. Hole circ. Pull all tubing. Pump down 4 1/2 casing mix 80 sk. 60/40 posmix, 10% gel 1/4 FC per sk. and 100# hulls. Cement circ. out of 8 5/8. Close in 8 5/8 squeeze in 5 sk. to 400# and SI.

Name of Plugging Contractor Berexco, Inc. License No. 5363

Address Box 723 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford


(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 723 Hays, KS 67601

Subscribed and sworn to before me this 24 day of August, 19 93



Rosemary Smith
 Notary Public

5-1-1995

My Commission Expires:
 USE ONLY ONE SIDE OF EACH FORM

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 26 1993

CONSERVATION DIVISION
 Wichita, Kansas