

15-051-02079-0000

Form CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec. 28 Twp. 11 Rge. 16 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines SE SW NW

Lease Owner Tomlinson-Kathol, Inc.

Lease Name Neilson Well No. 6

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced ~~XXXXXX~~ 11-8-66 19

Plugging completed 11-9-66 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey

Producing formation Depth to top Bottom Total Depth of Well 3419 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	942'	None
				5-1/2"	3395'	900'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, pushed plug to 995', ran 10 gal. of sand and dumped 5 sacks of cement with dump bailer. Pulled 5 1/2" casing, set 10' rock bridge @ 300' and dumped 40 sacks of cement. Mudded hole to 40', set rock bridge and ran 10 sacks of cement to base of cellar.

RECEIVED
NOV 14 1966
11-14-66
CONSERVATION DIVISION
WICHITA, KANSAS

PLUGGING COMPLETE.

Name of Plugging Contractor ~~knighx~~ KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or ~~KNIGHT CASING PULLING COMPANY~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of November, 1966

My commission expires May 20, 1968
Milton J. Volin Notary Public.

TOMLINSON & KATHOL

CONSULTING GEOLOGISTS

15-051-02079-0000

414 UNION CENTER

PHONE AM 7-3042

WICHITA 2, KANSAS

June 19, 1959

RECEIVED
NOV 14 1959
DIVISION
KANSAS

**Tomlinson-Kathol, Inc.
414 Union Center
Wichita, Kansas**

**Subject: Tomlinson-Kathol, Inc.
6 Nielsen
SE SW NW, Sec. 28-118-16W
Ellis County, Kansas**

Gentlemen:

The following is a sample analysis report of the above captioned well.

The well was under geological supervision from 2800 to 3375 feet, rotary total depth. Samples were examined from 2900 to 3375 feet, rotary total depth.

All tops and zones of porosity are based on kelly bushing measurements.

The following formation tops were determined from sample examination:

8 5/8" 942'

Elevation 1759 KB

Top Heebner	2935	-1176
Top Toronto	2956	-1197
Top Lansing	2982	-1223
Base Kansas City	3230	-1471
Top Conglomerate	3292	-1533
Top Arbuckle	3299	-1540
Rotary Total Depth	3375	-1616
5-1/2" Casing	3375	-1616

3299
1540

59

Note: Structurally on the Arbuckle the # 6 was nineteen (19) feet lower than # 5 to the west and fourteen (14) feet lower than # 3 to the south.