

15-155-19068-00-00

RECEIVED DEC 2 1970


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give Address Completely  
Make Required  
Mail or Deliver to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Reno County, Sec. 4 Twp. 26 Rge. 4 (E) (W)  
Location as "NE/CNWxSWx" or footage from lines 90' S C E/2 SW  
Lease Owner Rosen Oil Company  
Lease Name Beltz #1 Well No.  
Office Address Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 12/14/70 19  
Plugging completed 12/16/70 19  
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman  
Producing formation Depth to top Bottom Total Depth of Well 4103 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	186'	none
				5 1/2"	4101'	3188'

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 8 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 4103', ran sand to 4080' and ran 5 sacks of cement.  
Shot pipe at 3302', 3270', 3200', pulled 106 joints. Set 10' rock  
bridge at 215', ran 25 sacks of cement. Mudded to 40', 10' rock  
bridge and ran 100 sacks of cement. Tallied pipe.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF Kansas, COUNTY OF Rice, ss.  
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
Chase, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 18th day of December, 1970

My commission expires 2/15/71

Margaret Duda  
Notary Public

WELL LOG - Baltz #1

OPERATOR: Vaughn E. Wiggins  
 Box 191  
 McPherson, Kansas

LOCATION: ~~Q-N/2~~ - SE - SW  
 Sec. 4 - 26S - 4W  
 Reno County,  
 Kansas

CONTRACTOR: German Drilling Company  
 502 Petroleum Building  
 Wichita, Kansas 67202

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 12 1970  
 CONSERVATION DIVISION  
 Wichita, Kansas

Farm: Baltz -  
 Date Commenced: 9-17-64  
 Date Completed: 9-28-64 -

Well No. 1  
 Rotary

<u>From</u>	<u>To</u>	<u>Formation</u>
0	20	Clay and shale
20	186	Red Rock
186	870	Shale and shells
870	1150	Lime and shale
1150	1355	Lime and shale
1355	1488	Lime and shale
1488	1555	Lime and shale
1555	1685	Shale and Lime
1685	2040	Shale and lime
2040	2280	Shale and lime
2280	2350	Lime and shale
2350	2410	Lime and shale
2410	2490	Shale and Lime
2490	2700	Shale and lime
2700	2876	Shale and lime
2876	2897	Sand (Douglas)
2897	2980	Lime and shale (Lansing - K.C.)
2980	3118	Lime
3118	3163	Lime and shale
3163	3249	Lime and shale
3249	3310	Lime
3310	3348	Lime
3348	3433	Lime and shale
3433	3491	Lime
3491	3552	Shale-lime
3552	3591	Shale and sandy shale
3591	3660	Shale and lime
3660	3668	Chert (Miss.)
3668	3750	Lime and chert
3750	3783	Lime
3783	3816	Lime
3816	3823	Lime
3823	3864	Lime
3864	3885	Lime
3885	3935	Lime
3935	3955	Lime
3955	3969	Lime
3969	4030	Shale and lime
4030	4066	Shale
4066	4093	Lime
4093	4099	Shale
4099	4101	Lime (Viola)
4101	4103	Total depth

Cable Tool TD. 4103

I hereby certify that the foregoing is a true and correct copy of the Well Log for the Baltz #1, drilled for Vaughn E. Wiggins and completed September 28, 1964.

Surface: 186 8 5/8  
 Production: 4101 5 1/2

GERMAN DRILLING COMPANY

*Harvey F. German*  
 Harvey F. German - Owner

STATE OF KANSAS )  
 ) ss.  
 COUNTY OF SEDGWICK )

Subscribed, and sworn to, before the undersigned a Notary Public, in and for County and State aforesaid this twenty-ninth day of September, 1964.

*Geneva M. German*  
 Geneva M. German - Notary Public

My Commission expires February 28th, 1968.