


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County. Sec. 30 Twp. 11S Rge. 16 (E) W (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW%SW%" or footage from lines SE SE SW
Lease Owner Tennessee Gas Transmission Co.
Lease Name Lydia DeHoff Well No. /
Office Address P.O. Box 163, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Dec. 13, 19 57
Application for plugging filed Dec. 13, 19 57
Application for plugging approved Dec. 13, 19 57
Plugging commenced Dec. 13, 19 57
Plugging completed Dec. 13, 19 57
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert P. Leiker, 805 Main St., Victoria, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3480 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	203	8 5/8"	203	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

From 3480' to 744' - heavy rotary mud
744' to 667' - 1/2 sack hulls, 25 sacks cement
667' to 200' - heavy rotary mud
200' to 138' - 1/2 sack hulls, 20 sacks cement
138' to 40' - heavy rotary mud
40' to 6' - 1/2 sack hulls, 10 sacks cement
6' to surface - cellar

RECEIVED
STATE CORPORATION COMMISSION
DEC 20 1957
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Peel Brothers, Inc.
Address P.O. Box 88, Hoisington, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Peel Brothers, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. PEEL BROTHERS, INC.

(Signature) BY: Al H. Smith
P.O. Box 88, Hoisington, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of December, 19 57

My commission expires April 27, 1960

Notary Public.

PLUGGING
FILE SEC 30 T. 11 R. 16
BOOK PAGE 69 LINE 45

DRILLERS' LOG

Well Owner: Tennessee Gas Transmission Co.
 Farm Name: Lydia DeHoff #1
 Commenced: 12/2/57
 Completed: 12/13/57
 Total Depth: 3480'
 Casing: 8 5/8" @ 203' con.

SE SE SW
 Sec. 30-119-16W,
 Ellis County, Kansas

Elevations:

Contractor: Peel Brothers, Inc.

Production: Dry

Figures below indicate bottoms of formations:

Shale	0 -	20
Post rock		45
Shale and sand		340
Red rock		590
Sand		700
Red rock		810
Shale and shells		1050
Anhydrite		1085
Shale		1795
Shale and lime		1970
Lime		2205
Lime and shale		2500
Shale		2655
Shale and lime		2885
Lime		2948
Lime and shale		3100
Lime		3250
Lime and shert		3325
Lime		3390
Conglomerate		3404
Lime		3480
Total Depth		3480

This is to certify that the above information is to the best of our knowledge, true and correct.

PEEL BROTHERS, INC.

BY: Al H. Smith

SUBSCRIBED AND SWORN to before me this 17th day of December, 1957

My commission expires: April 27, 1960

Ruth Brank
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 12-20-1957
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE NO. 30 T 11 R 16 W
 BOOK PAGE 69 LINE 45