

STATE OF KANSAS  
STATE CORPORATION COMMISSION

OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Ellis

County. Sec. 30 Twp. 11 Rge. (E) 16 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines 330'S 330'E of W 1/4 Corner

Lease Owner Cities Service Oil Co

Lease Name DeHoff

Well No. 3

Office Address Bartlesville Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9-10-43 19

Application for plugging filed 9-10-43 19

Application for plugging approved 9-10-43 19

Plugging commenced 9-10-43 19

Plugging completed 9-10-43 19

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well C. T. Alexander

Producing formation Arbuckle Depth to top 3415 Bottom Total Depth of Well 3453 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle Lense	Dry			8 7/8	1035'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Total Depth 3453' Dumped Cement To 3400' Mud  
3400' To 300' Set Cement Bridge @ 300' Mud To 26' Cement To  
2' Mud & Duct To Surface

30 11 16W  
91 5

10-21-1943

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Mr. B. L. Humber

Address Cities Service Oil Co Cicot Bend, Kansas

STATE OF Kansas COUNTY OF Barton ss.

(employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-  
described well as filed and that the same are true and correct. So help me God.

(Signature)

Cities Service Oil Co Russell, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 14th day of September, 1943

My Commission Expires Mar. 12, 1947

My commission expires

Notary Public.

WELL RECORD

Company Cities Service Oil Co. Well No. 3 Farm DeHoff  
 Location 330' South and 330' East of W/4 Corner Sec. 30 T. 11 R. 16W  
 Elevation 1839 County Ellis State Kansas  
 Drlg. Comm. August 22, 1943 Contractor Holm Drilling Company  
 Drlg. Comp. September 10, 1943 Acid None  
 T. D. 3453' Initial Prod. Dry - Plugged and Abandoned

CASING RECORD:

8-5/8" @ 1035' con. 350 ex Lone Star and 300# C. C.

FORMATION RECORD:

shale & shells 0-360  
 iron 372  
 shale & shells 495  
 sand & iron shells 730  
 shale & shells 1000  
 shale 1020  
 anhydrite & lime 1055  
 shale red & shells 1390  
 salt, shale & shells 1575  
 shale & shells 1665  
 lime & shale breaks 2080  
 lime 2204  
 shale red 2214  
 lime 2310  
 shale 2335  
 lime 2460  
 lime & shale breaks 2780  
 lime 3088  
 lime & shale breaks 3205  
 lime 3358  
 conglomerate 3369  
 lime 3395  
 lime, shale & chert 3450  
 lime 3453 T. D.

Top Xros. Arbuckle 3401'  
 Top Arbuckle 3415'  
 Penetration 38'  
 Total Depth 3453'

No shows.

Syfo: 500' 1°  
 1000' 1°  
 1500' 0°  
 2000' 0°  
 2500' 1°  
 3000' 0°

30 11 16W  
 91 5

10-21-1943