


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County, Sec. 30 Twp. 11S Rge. 16W (E) (W)

Location as "NE/CNW%SW%" or footage from lines SE SW SE

Lease Owner Hinkle Oil Company

Lease Name Eddie Well No. 1

Office Address 1016 Union Center

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed August 25 19 63

Application for plugging filed August 25 19 63

Application for plugging approved August 25 19 63

Plugging commenced August 25 19 63

Plugging completed August 25 19 63

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3521 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	310'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set bottom plug @ 480'
20 sx cement thru drill
pipe. Filled w/heavy mud
to 240'. Set middle plug
@ 240' w/20 sx cement thru
drill pipe. Filled w/heavy
mud to 40' to plug @ 40'.
10 sx cement, filled to base
of cellar.

RECEIVED
STATE CORPORATION COMMISSION
AUG 29 1963
8-29-1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company

Address Box 173--Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

George A. Angle (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) George A. Angle

1720 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of August, 19 63

My commission expires 11-17-66

Dwayne D. Head
Notary Public.



DRILLING LOG

Log No. 1

CASING RECORD: 8 1/8" @ 310'
w/200 ex cement

COMPANY: Noble Oil Company

CONTRACTOR: Red Tiger Drilling Co.

COMMENCED: August 16, 1963

COMPLETED: August 25, 1963

DESCRIPTION: SE SW SE
30-118-10W
Ellis Co.,
Kansas

ELEVATION:

TOTAL DEPTH: 3521'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay & Shale	0	430	
Shale & Shells	430	680	
Sand	680	785	
Shale & Red Bed	785	1124	
Anhydrite	1124	1162	
Shale & Shells	1162	1445	
Shale Lime & Shells	1445	1800	
Lime & Shale	1800	2070	
Lime	2070	2205	
Lime w/Shale Streaks	2205	2326	
Lime & Shale	2326	2885	
Lime	2885	3450	
Lime & Chert	3450	3480	
Lime Chert & Shale	3480	3521	

RECEIVED
STATE CORPORATION COMMISSION
8-29-1963
AUG 29 1963

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

George A. Angle
George A. Angle

Subscribed and sworn to before me this 29th day of August, 1963.

Dwayne V. [Signature]
Notary Public

My Commission Expires:

11-17-68