


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas



Locate well correctly on above  
Section Plat

Ellis County, Sec. 30 Twp. 11S Rge. (E) 16 (W)  
Location as "NE/CNW%SW%" or footage from lines 330' FNL & 330' FWL  
Lease Owner Cities Service Oil Company  
Lease Name DeHoff Well No. 1  
Office Address Box 553 Russell, Kansas 67665  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 5-19 1942  
Application for plugging filed 9-25 1969  
Application for plugging approved 9-26 1969  
Plugging commenced 11-1 1969  
Plugging completed 11-7 1969  
Reason for abandonment of well or producing formation No longer economical -  
no remedial possibilities  
If a producing well is abandoned, date of last production 9-1 1969  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Leo Massey  
Producing formation Arbuckle Depth to top 3333' Bottom 3368' Total Depth of Well 3368 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1084'	None
				5 1/2"	3366'	2443'

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 13 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole W/sand 3368' to 3300'  
Dumped 5 Sx. Cement 3300' to 3260'  
Filled hole W/hvy. mud 3260' to 425'  
Put in rock bridge 425' to 400'  
Welded on 8 5/8" Slip collar  
Put in 8 5/8" wooden plug  
Pumped in 150 sx. Pozmix plus 2% gel. at 500# Filling hole to bottom of cellar.  
Cut off 8 5/8" casing and welded on cap


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Co., Inc.  
Address Box 405 Chase, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.  
E. W. Peterman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *E. W. Peterman*  
Box 553 Russell, Kansas 67665 (Address)

SUBSCRIBED AND SWORN to before me this 12th day of November, 1969



10-5-72  
*James F. Kyger*  
Notary Public.

WELL RECORD

Company Cities Service Oil Co. Well No. 1 Farm DeHoff  
 Location 330' south and 330' east of NW Corner Sec. 30 T. 11 R. 16W  
 Elevation 1844 County Ellis State Kansas  
 Drig. Comm. April 30, 1942 Contractor Mabee Oil & Gas Company  
 Drig. Comp. May 19, 1942 Acid 2500 gals. - May 20, 1942  
 T. D. 3368' Initial Prod. Rehometer Potential: 2991 oil, no water, 24 hrs.

GASING RECORD:

8-5/8" @ 1038' cem. 300 sx Ash Grove  
 and 300# C. C.  
 5-1/2" @ 3334' cem. 100 sx Lone Star

Corr. Top Arbuckle 3333' (-1489)  
 Penetration 35'  
 Total Depth 3368'

FORMATION RECORD:

shale & shells 0-470  
 sand 530  
 sand & shale 690  
 shale, shells & red bed 885  
 red bed 1020  
 shale 1038  
 anhydrite 1070  
 red bed & shale 1375  
 shale & salt 1575  
 shale & shells 1630  
 lime & shale 1958  
 lime broken 2101  
 shale & lime 2202  
 sand & shale 2225  
 shale & lime 2240  
 lime & shale 2525  
 shale & lime shells 2605  
 shale & shells 2812  
 lime 3025  
 3025 = 3020 SIM  
 lime 3209  
 lime broken 3305  
 lime 3335  
 3335 Rot. TD = 3336 SIM  
 dolomite 3368 T. D.

Fillup: 100' oil in 1 hour  
 200' oil in 2 hours  
 800' oil in 7 hours  
 1000' oil in 9 hours  
 2000' oil in 15 hours

Syfo: 500' 00  
 1000' 10  
 1500' 10  
 2000' 10  
 2500' 00  
 3000' 00

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 13 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

Elw.  
 #1 - 1844  
 2 - 1870  
 3 - 1839 Dry Hole.  
 4 - 1835  
 5 - 1876  
 Part -