

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Russell County. Sec. 18 Twp. 13 Rge. 13 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____

NE SW SW
Lease Owner ~~xKilianx~~ Mai Operations
Lease Name Kilian Well No. A #1

Office Address Box 33 - Russell, Ks. 67665
Character of Well (Completed as Oil, Gas or Dry Hole) _____

Dry Hole
Date Well completed 90-27 1978 19
Application for plugging filed 9-27 1978
Application for plugging approved 9-27 1978
Plugging commenced 9-27 1978
Plugging completed 9-27 1978
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plot

If a producing well is abandoned, date of last production 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3290
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug @ 500' with 50 sacks 50/50 pozmix, 2% Gel thru drill pipe
Middle plug @ 240' with 25 sacks " " " " " "
Top plug @ 40', $\frac{1}{2}$ sk. hulls, plug & 10 sks. cement.
2 sacks cement in rat hole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leonard Williamson
Box 823 - Great Bend, Ks. 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 29 day of September, 1978

Dorothy M. Hague
Notary Public.

My commission expires April 11, 1982



RECEIVED
STATE CORPORATION COMMISSION

OCT - 3 1978
10-03-1978
CONSERVATION DIVISION
Wichita, Kansas

15-167-21235-00-00

DRILLERS' WELL LOG

DATE COMMENCED: September 22, 1978
DATE COMPLETED: September 27, 1978

Mai Operations
KILIAN A #1
NE SW SW
Sec. 18-T13S-R13W
Russell, County, Kansas

0 -	100'	Clay & Post Rock
100 -	268'	Blue Shale
268 -	280'	Red & Blue Shale
280 -	285'	Sand
285 -	380'	Shale & Sand
380 -	888'	Anhydrite
888 -	1145'	Red Bed
1145 -	1475'	Shale & Shells
1475 -	2701'	Lime & Shale
2701 -	2724'	Lime
2724 -	2740'	Shale
2740 -	2968'	Lime
2968 -	2972'	Shale
2972 -	2985'	Lime & Shale
2985 -	3003'	Lime
3003 -	3024'	Shale
3024 -	3290'	Lime
	3290'	RTD

ELEVATION: 1853 K.B.

FORMATION DATA

ANHYDRITE	849
HOWARD	2701
SEVERY	2724
TOPEKA	2740
MEHNER	2968
TORONTO	2985
DOUGLAS	3003
KANSAS CITY	3024
RTD	3090

SURFACE PIPE / Set 2-5/8"
32# pipe @ 250' with 160
sacks cement, 2 1/2 Gal, 3cc.

AFFIDAVIT

State of Kansas
County of Barton (ss.

Leonard Williamson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 29 day of September 1978.

Deborah M. Nagle

Notary Public

My Comm. Expires: 11-1982

RECEIVED
STATE CORPORATION COMMISSION

OCT - 3 1978
10-03-1978
CONSERVATION DIVISION
Wichita, Kansas