

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING REPORT
K.A.R.-82-3-117

23223

API NUMBER 15-167-~~23223~~-0000

LEASE NAME Smith-Ehrlich

WELL NUMBER 1

1650 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 20 TWP. 13S RGE. 13 (E) or (W)

COUNTY Russell

Date Well Completed 10-21-02

Plugging Commenced 10-21-02

Plugging Completed 10-21-02

LEASE OPERATOR Jason Oil Company

ADDRESS P.O. Box 701, Russell, Kansas 67665

PHONE (785) 483-4204 OPERATORS LICENSE NO. 6622

Character of Well D&A

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on 10-21-02 (date)

by Hays (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 3120'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each so
Plugged with 130 sacks 60/40 Poz., 6% Gel., 1/4# flocele per sack. 1st. plug - 25 sacks @ 825', 2nd. plug - 70 sacks @ 550', wiper plug - 10 sacks @ 40' to surface, rat hole - 15 sacks, mouse hole - 10 sacks

Name of Plugging Contractor Allied Cementing Company, Inc. License No. _____


Address P.O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Jason Oil Company

STATE OF KANSAS COUNTY OF Russell, ss.

James L. Schoenberger (Notary Public) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.
(Signature) James L. Schoenberger

(Address) P. O. Box 701, Russell, KS 67665-0701



AND SWORN TO before me this 21st day of November, XX 2002

Fred Weigel, Jr.
Fred Weigel, Jr. Notary Public

My Commission Expires: July 18, 2006

USE ONLY ONE SIDE OF EACH FORM

COPY

15-167-23223-00-00

ORIGINAL

DRILLERS WELL LOG

Date Commenced: October 15, 2002
Date Completed: October 21, 2002

Jason Oil Company
Smith-Ehrlich #1
SE NW SW Sec. 20-13S-13W
Russell County, Kansas

Elevation: 1801' G.L.
1806' K.B.

0 - 493' Clay & Shale
493 - 550' Shale & Shells
550 - 795' Clay & Shale
795 - 839' Anhydrite
839 - 1170' Shale
1170 - 1565' Shale & Shells
1565 - 1880' Shale, Lime & Shells
1880 - 2095' Shale
2095 - 2310' Shale & Sand
2310 - 2600' Shale & Lime
2600 - 2925' Shale
2925 - 3100' Lime & Shale
3100 - 3320' Shale
3320' R.T.D.

RECEIVED
NOV 26 2002
KCC WICHITA

FORMATION DATA

Anhydrite 795'
Base Anhydrite 839'
Topeka 2700'
Lansing Kansas City 3200'
Base Kansas City 3320'

Surface Pipe: Set 23#, new, 8 5/8" casing @ 493' with 225 sacks 60/40 Poz., 2% Gel., 3% CC.

A F F I D A V I T

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

Alan Vonfeldt of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Alan Vonfeldt
Alan Vonfeldt

Subscribed and sworn to before me this 26th day of October, 2002.

My Commission Expires:

August 30, 2003

Cheryl M. Payne
Cheryl M. Payne, Notary Public

