

10 15-007-16667-00.00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 20 Twp. 32 Rge. 13 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines SW SW SW
Lease Owner Morgenstern & Specter, Inc.
Lease Name Hopkins Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 3-15-60 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 11-30-61 19
Plugging completed 12-2-61 19
Reason for abandonment of well or producing formation Depleted

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes Yes

Name of Conservation Agent who supervised plugging of this well Fred Hample
Producing formation Mississippi Depth to top 4505 Bottom 4570 Total Depth of Well 4572 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	219'	None
				4-1/2"	4570'	4132'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4572', ran sand to 4550' and dumped 5 sacks of cement @ 4550' with dump bailer. Pulled 4 1/2" casing. Mudded hole to 220', set 10' rock bridge to 210' and ran 20 sacks of cement @ 210'. Mudded to 35', set 5' rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

JAN 17 1962

CONSERVATION DIVISION

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or ~~XXXXXX XXXXX~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of December, 1961

Milton J. Volin
Notary Public.

My commission expires May 20, 1964



15-007-16667-00-00
 WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

COPY


From
 Representative of
 Russell Power

Company. STRATA DRIG. & PETROLEUM DEV. CO.
 Farm. Hopkins No. 1

SEC. 20 T. 32 R. 13W
 SW SW SW

Total Depth. 4570'
 Comm. 3-1-60 Comp. 3-15-60
 Shot or Treated.
 Contractor. Strata Drlg.
 Issued. 12-3-60

County Barber
 KANSAS



CASING:
 8 5/8" 219' cem w/175 sx.
 4 1/2" 4570' cem w/75 sx.

Elevation. Est. 1798' KB

Production. 23 BOPD

Figures Indicate Bottom of Formations.

red bed	1422
shale & lime	2745
shale & lime streaks	2912
lime & shale	3960
shale	4033
lime	4570
Total Depth	

TOPS: SCOUT	
Heebner	3850
Brown Lime	4029
Lansing	4038
Marmaton	4445
Mississippi	4505

RECEIVED
 STATE COMMISSION

JAN 22 1962

CONSERVATION DIVISION
 Wichita, Kansas

DST #1 4463-4498', op 45 mins., weak blow, rec. 15' mud, IFP 735#, FFP 0#, BHP 290#/20 mins.

DST #2 4498-4522', op 1 hr, gas to surf in 14 min., to small to meas. Rec. 190' fluid, 100' gas cut mud, 80' slightly oil cut mud, 10' oil cut mud. BHP 1615#/2 min still building.

DST #3 4522-4540', op 2 hrs., rec. 110' slightly oil cut mud. IFP 65#, FFP 80#, BHP 155#/20 min.