


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Ellis

County. Sec. 34 Twp. 11S Rge. (E) 16 (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW%SW%" or footage from lines SW NE SW
Lease Owner C. U. Bay
Lease Name Chrisler Well No. 1
Office Address Box 513 Chase Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 15 19 55
Application for plugging filed (oral) February 15 19 55
Application for plugging approved February 18 19 55
Plugging commenced February 15 19 55
Plugging completed February 15 19 55
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3490 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	229'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole from TD. 3490' to 210'.
Plug at 210' w/20 sack cement on top through drill pipe
Mudded to 40'
Plug at 40' w/1/2 sack of hulls and 10 sacks cement.
Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company
Address Sterling Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
Forrest Crawford (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Forrest Crawford
(Address) _____

SUBSCRIBED AND SWORN TO before me this 21 day of February 19 55

My commission expires May 20 1958

Vincent O. Gray
Notary Public.

PLUGGING
FILE NO. 343 11 R 16 W
BOOK 98 PAGE 13 LINE 13

RECEIVED
FEB 23 1955
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

15-051-19236-00-00

CHRISLER #1

Location SW NE 1/4, Section 34-118-16W,
Ellis County, Kansas

OWNER: G. V. Bay

NOTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: 2-2-55

COMPLETED: 2-15-55

ROTARY TOTAL DEPTH: 3490'

LOG

CASING RECORD

0-230	Surface Soil, Shale & Shells
230-340	Shale
340-445	Sand
445-1025	Shale & Red Bed
1025-1065	Anhydrite
1065-1525	Shale & Shells
1525-1650	Shale
1650-2240	Limestone
2240-2665	Limestone & Shale
2665-2785	Shale
2785-3330	Limestone
3330-3490	Conglomerate T.D.

Ran 229' of 8-5/8" casing set with
150 sacks cement.

PRODUCTION

Plugged & Abandoned

PLUGGING
 FILE SEC. 34 T. 11 R. 16W
 BOOK PAGE 98 LINE 13

RECEIVED
 COMMISSION
 2-23-1955
 FEB 23 1955
 CONSERVATION DIVISION
 Wichita, Kansas