


15-051-20319-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Ellis County, Sec. 34 Twp. 11S Rge. (E) 16 (W)

Location as "NE/CNW&SW&" or footage from lines NW SW NW
Lease Owner Herman George Kaiser, Oil Producer
Lease Name Chrisler Well No. F-1
Office Address 909 Palace Bldg., Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-30 19 68
Application for plugging filed 9-30 19 68
Application for plugging approved 9-30 19 68
Plugging commenced 9-30 19 68
Plugging completed 9-30 19 68
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 3005 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	257'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged @ 600' with 70 sacks 50-50 Posmix 6% Gel. Plugged @ 240' with 20 sacks 50-50 Posmix 6% Gel. Bridge @ 10' with 10 sacks 50-50 Posmix 6% Gel.

RECEIVED
STATE CORPORATION COMMISSION
OCT 2 - 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of October, 19 68

My commission expires April 1, 1971

Ulanda Nichols

Notary Public.

DRILLER'S LOG

COMPANY	Herman George Kaiser, Oil Producer
CONTRACTOR	LEBEN DRILLING, INC.
FARM	CHRISLER F-1
LOCATION	NW SW NW SECTION 34-11S-16W ELLIS COUNTY, KANSAS
COMMENCED	9-25-68
COMPLETED	9-30-68

0	100	Clay, Shale
100	257	Shale, Sand
257	350	Shale, Red Bed
350	540	Sand, Shale
540	670	Sand
670	983	Shale, Red Bed
983	1021	Anhydrite
1021	1570	Shale
1570	2060	Lime, Shale
2060	2645	Lime
2645	2775	Shale, Lime
2775	2963	Lime, Shale
2963	3005	Lime
	<u>3005</u>	<u>RTD - D. & A.</u>

RECEIVED
STATE CORPORATION COMMISSION
OCT 2 - 1968
CONSERVATION DIVISION
Wichita, Kansas

8 5/8" 20# new surface casing set @ 257' cemented with 160 sacks
Common cement, 2% cc


I, Leslie Kite, do hereby certify that the above and foregoing is
a true and correct copy of the log of the Chrisler #F-1 Well, located
NW SW NW of Section 34, Township 11 South, Range 16 West, Ellis
County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
Leslie Kite

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in
and for Barton County, Kansas, this 1st day of October, 1968.

Ulanda Nichols
Ulanda Nichols



My Commission Expires:
April 1, 1971