

# 2

LEASE NAME Loewen "C"

WELL NUMBER 2

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

1650 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 18 TWP. 21 SRGE. 3 (E) ~~XXXX~~

COUNTY Marion

LEASE OPERATOR Knighton Oil Company, Inc.

221 South Broadway-#710

ADDRESS Wichita, Kansas 67202

PHONE# (316) 264-7918 OPERATORS LICENSE NO. 5010

Date Well Completed 9/05/56

Character of Well Oil

Plugging Commenced 7/06/92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7/06/92

The plugging proposal was approved on 7/06/92 (date)

by Ralph Tittel (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Hunton Depth to Top 2825 Bottom UNK T.D. 2840

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Hunton	Oil	Surf	104	8-5/8"	104'	None
		Surf	2840	5 1/2"	2840'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped 200 sacks 60/40 Poz Mix, 4% Gel into casing. Cement circulated on backside from 520' to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor United Cementing & Acid Co., Inc. License # STATE CORPORATION COMMISSION

2510 West 6th, P. O. Box 712

Address El Dorado, Kansas 67042

RECEIVED  
 JUL 17 1992  
 CONSERVATION DIVISION  
 Wichita, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Knighton Oil Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Earl M. Knighton, Jr.

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above described well as filed the the same are true and correct, so help me God.


(Signature) Earl M. Knighton, Jr.

(Address) 221 S. Broadway-#710, Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 16th day of July, 19 92

Sarah A. Simon  
 Notary Public  
 Sarah A. Simon

My Commission Expires: 12/11/93



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


COPY

Company. CITIES SERVICE OIL  
Farm. Loewen "C" No. 2

SEC. 18 T. 21 R. 3E  
S<sup>2</sup>/4 NE SW  
990' W 990' S of Cen.

Total Depth. 2840'  
Comm. 8-30-56 Comp. 9-5-56  
Shot or Treated.  
Contractor. White & Ellis Drlg. Co.  
Issued. 12-8-56

County Marion  
KANSAS



Elevation. 1164' RTB (5' above G.L.)

Production. 96 BO

CASING:

8" 104' w/70 sx cem.  
5 1/2" 2826' w/150 sx cem.

All Meas. fr RTB

soil	2
clay	25
shale	62
lime	72
shale	81
lime	90
shale	98
lime	105
anhydrite	220
lime	280
shale-red bed	325
lime	425
lime-shale	550
lime	650
shale	695
shale-red rock	730
shale-lime	835
lime	880
shale	1074
sdv lime	1140
shale-lime	1214
shale	1314
lime	1500
shale	1600
sand	1620
lime-shale	1705
sand-shale	1740
shale	1750
lime	1833
shale-lime	1860
sand	1942
lime	1995
shale -lime	2030
lime	2443
shale-lime	2621
chert	2686
lime	2712
shale-lime	2720
shale	2725
lime	2840
Total Depth	

Figures indicate Bottom of Formations.

Top Misener sand	2824 1/2' (-1363 1/2')
Base	2825' No oil noted.
Top Hunton Ls.	2825' (-1364)
Pen.	15' S.O.
2825-28'	Dol., wh., fn. xn., sl. med. por., S.S.O.
2828-40'	Dol., tan, fn. med. xn., sucrosic, good por., G.S.F.O.

DST #1, 2826-2840' Open 1 hr. Closed 20 min. stron blow immediatly contiued for 45 min. Weakening to fair in 1 hr. IF 90#, FF 980#, BHP 1010#. Rec. 2650' oil, 100' drlg. fluid, no wtr.

Ran Schlumberger.  
This well was not shot.

Steel Line Meas.	S.H.S.
1080' = 1080'	1080' O.K.
1525' = 1525'	1525' O.K.
2029' = 2029'	2029' O.K.
2526' = 2526'	2526' O.K.
2761' = 2761'	2761' O.K.

Top Douglas sand	1824' (-360)
Base	1940 no oil noted.
Top Lansing Ls.	2037' (-573)
Base	2154' no oil noted.
Top Kansas City Ls.	2169' (-705)
Base	2414' No oil note.
Top Mississippi	2621' (-1157)
Base	2684' No oil noted.

K. G. S. LIBRARY

RECEIVED  
STATE CORPORATION COMMISSION

JUL 17 1992

CONSERVATION DIVISION  
Wichita, Kansas