

RECEIVED

Corrected CP-4
from # 4-21

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date

AUG 20 2010

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form CP-4
March 2009

Type or Print on this Form
Form must be Signed
All blanks must be Filled

KCC DODGE CITY WELL PLUGGING RECORD
K.A.R. 82-3-117

OPERATOR: License #: 5056
Name: F.G. Holl Company, L.L.C.
Address 1: 9431 E. Central, Suite 100
Address 2: _____
City: Wichita State: KS Zip: 67206 + _____
Contact Person: Franklin R. Greenbaum
Phone: (316) 684-8481, Ext. 206
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Conglomerate Depth to Top: 3342 Bottom: 3350 T.D. 3431
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 15-185-20,849-00-00
Spot Description: _____
SE NW NE Sec. 21 Twp. 21 S. R. 11 East West
4,290 Feet from North / South Line of Section
1,650 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Stafford
Lease Name: SMITH ESTATE "B" Well #: 3-21
Date Well Completed: 9/1978
The plugging proposal was approved on: _____ (Date)
by: _____ (KCC District Agent's Name)
Plugging Commenced: 6/5/2008
Plugging Completed: 6/5/2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Conglomerate	oil	Surface	8-5/8"	311	
		Production	4-1/2"		

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set bridge plug @ 3375', bailed 2 sacks cement on plug, set bridge plug at 725', bailed 2 sacks cement on plug. Pressure tested casing, held at 300 psi. Shot holes at 690', tied on to 4-1/2" casing, circulated with 200 sacks to surface, cut casing head off, cleaned up location.

Plugging Contractor License #: 31925 Name: Quality Well Service
Address 1: 190 US Highway 56 Address 2: _____
City: Ellinwood State: KS Zip: 67526 + _____
Phone: (620) 938-2388
Name of Party Responsible for Plugging Fees: F.G. Holl Company, L.L.C.
State of KS County, Sedgwick, ss.
Loveness Mpanje Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained; and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Loveness Mpanje