

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-051-22567-00-00

API NUMBER 15-051-22567

LEASE NAME Orlan Carmichael

WELL NUMBER 3

4110 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 4 TWP. 115 RGE. 17 (E) or (W)

COUNTY Ellis

Date Well Completed 3-18-92

Plugging Commenced 4-13-92

Plugging Completed 4-13-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Helmerich & Payne, Inc.

ADDRESS Box 558, Garden City, KS 67846

PHONE#(316) 276-3693 OPERATORS LICENSE NO. _____

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-18-92 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Penn-Congh Depth to Top 3432 Bottom 3495 T.D. 3519

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Toronto	water	3130	40	4 1/2		0
Lansing-KC	water	3150	3388	4 1/2		0
Penn Congh	oil	3440		4 1/2		0
Arb	water	3530	3519		3525	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3420 feet to _____ feet each section. Perf 4 1/2" csg @ 1160 & 600 - ran 2-3/8 tbg to 3420' Pump 25-# Hulls. 75 sxs 60/40 Poz. Pull tbg to 1920' Circ to surface w/ 95 sxs 60/40 Poz - 10% Gel - Pull tbg. Pump dn csg w/ 100# Hulls - 95 sxs 60/40 Poz 10% gel at 400# - Hook up to csg. Pump 55 sxs cmt.w/ 108# Hulls Max press 700# SI at 600# - total cmt 320 sxs 60/40 poz.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B.J. License No. _____

Address Hays, KS

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Helmerich & Payne, Inc.

4-21-1992
APR 21 1992

STATE OF Kansas COUNTY OF Finney, ss.

CONSERVATION DIVISION

Helmerich & Payne, Inc. (Employee of Operator or Owner (Operator))
above-described well, being first-duly sworn on oath, says: That I have knowledge of the fact
statements, and matters herein contained and the log of the above-described well as filed with
the same are true and correct, so help me God.

(Signature) Melvin Lunday

(Address) Box 558, Garden City, KS 67846

SUBSCRIBED AND SWORN TO before me this 20th day of April, 1992

Judy Richman
Notary Public

My Commission Expires: August 15, 1992