

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION 15-051-01172-00-01
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER N.A. OWWO (of this well) 6/89
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Helmerich and Payne, Inc. OPERATORS LICENSE NO. 5293

ADDRESS P.O. Box 558 Garden City, Kansas 67846 PHONE # (316) 276-3693

LEASE (FARM) Roy Carmichael WELL NO. #3 WELL LOCATION C N/2 NE SW COUNTY Ellis

SEC. 4 TWP. 11 RGE. 17 (E) or (W) TOTAL DEPTH 3937 PLUG BACK TD Same

Check One:

OIL WELL _____ GAS WELL _____ D & A _____ SWD or INJ WELL X DOCKET NO. CD 117911
C-19708

SURFACE CASING SIZE 15" SET AT 60' CEMENTED WITH 90 SACKS

CASING SIZE 5 1/2 SET AT 3690 CEMENTED WITH 150 SACKS

PERFORATED AT Open Hole 3690 to 3937 TOC approximately 2940

CONDITION OF WELL: GOOD _____ POOR X CASING LEAK X JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Spot 150 sk CIA plug thru tubing at 3345.

Pull tubing out and SDFD. Run tubing and tag plug. Set three 100 sks 60/40 poz, 6% gel plugs

(300 sks total) from TOC to surface. Attempt to squeeze 100 sks 60/40 poz. 6% gel down 5 1/2 x

(If additional space is needed use back of form) 10 3/4 annulus as per
Marion Schmidt KSCC, Hays

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon approval.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Lee Fellhoelter PHONE # (913) 434-4667

ADDRESS Box 394, Plainville, Kansas

PLUGGING CONTRACTOR Halliburton LICENSE NO. _____

ADDRESS Hays, Kansas PHONE # () _____

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Ken Geddek
(Operator or Agent)

DATE: 3-15-89

(4)



15-051-01172-00-01

Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH McCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE
JUN 20 1989

March 20, 1989

EXPIRES

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

Helmerich & Payne, Inc.
P. O. Box 558
Garden City, KS 67846

Roy Carmichael #3 (SWD)
C N/2 NE SW
Sec. 04-11S-17W
Ellis County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
Shari Feist Albrecht
Director

District: #4 2301 E. 13th
Hays, KS 67601
(913) 628-1200