

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 6170
Name: Globe Operating, Inc.
Address 1: P.O. Box 12
Address 2: _____
City: Great Bend State: KS Zip: 67530 + 0012
Contact Person: Richard Stalcup
Phone: (620) 792-7607
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 185-22152-0002
Spot Description: _____
NE SW NW Sec. 10 Twp. 22 S. R. 12 East West
1815 3473 Feet from North / South Line of Section
990 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Stafford
Lease Name: Spangenberg Well #: 2-10
Date Well Completed: _____
The plugging proposal was approved on: 08/13/2010 (Date)
by: Richard Lacey (KCC District Agent's Name)
Plugging Commenced: 08/18/2010
Plugging Completed: 08/19/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8-5/8"	250'	0'
		Production	5-1/2"	3662'	1580'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

08/18/10 - Drive to location. Sand well back to 3300'. Rig up jacks. Pull stretch 1692' of free pipe. Clean tools. Shut down for day.

08/19/10 - Drive to location. Rig up Log-Tech. Spot 5 sacks cement on top of sand. Shot casing off @ 1580'. 1st plug @ 660' - 10 sacks gel, 50 sacks 60/40 4% gel. 2nd plug @ 280' - 50 sacks 60/40 4% gel. 3rd plug @ 40' - 20 sacks 60/40 4% gel. Cement did circulate. Recovered 50 jts of 5-1/2" casing. Rig jacks down. Tally casing. Rig down. Clean tools & location.

Plugging Contractor License #: 6901 Name: D.S. & W. Well Servicing, Inc.
Address 1: 1822 24th Street Address 2: _____
City: Great Bend State: Kansas Zip: 67530 + _____
Phone: (620) 793-5838

Name of Party Responsible for Plugging Fees: Globe Operating, Inc.
State of Kansas County, Barton, ss.
Tim Dickson Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Tim Dickson

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

AUG 25 2010

KCC WICHITA