

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4

March 2009

Type or Print on this Form

Form must be Signed

All blanks must be Filled

OPERATOR: License #: 31070  
 Name: Eagle River Energy Corporation  
 Address 1: 7060 S. Yale, Suite 702  
 Address 2: \_\_\_\_\_  
 City: Tulsa State: OK Zip: 74136 + \_\_\_\_\_  
 Contact Person: Mark Godsey  
 Phone: (918) 494-8928  
 Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (If needed attach another sheet)  
LKC Depth to Top: 2998 Bottom: 3270 T.D. 3293  
Arbuckle Depth to Top: 3282 Bottom: 3293 T.D. 3293  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 167-30517-00-01  
 Spot Description: \_\_\_\_\_  
NE NW SE Sec. 7 Twp. 15 S. R. 13  East  West  
2,310 Feet from  North /  South Line of Section  
1,650 Feet from  East /  West Line of Section  
 Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
 County: Russell  
 Lease Name: Maag Well #: 3  
 Date Well Completed: 1966  
 The plugging proposal was approved on: 06/25/10 (Date)  
 by: Steve Bond (KCC District Agent's Name)  
 Plugging Commenced: 07/30/10  
 Plugging Completed: 07/30/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Lansing-KC	oil, water	surface; production	8 5/8; 5 1/2	440; 3291	None
Arbuckle	oil, water	surface; production	8 5/8; 5 1/2	440; 3291	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforate @ 850'. Ran 2 3/8" tbg to 923'. Pumped 150 sx 60/40 poz 4% gel. Added 500# c/s hulls and pumped 75 sx cement. Circulated well. Lay down tubing then pumped 25 sx cement down backside. Install bell nipple on casing. Pumped 25 sx cement, pressured to 300 psi, shut-in. Allied Cement performed cementing job.

RECEIVED

AUG 16 2010

Plugging Contractor License #: 34147 Name: Ace Well Service, Inc.  
 Address 1: PO Box 606 Address 2: \_\_\_\_\_  
 City: Russell State: KS Zip: 67665 + \_\_\_\_\_  
 Phone: (785) 445-2942

KCC WICHITA

Name of Party Responsible for Plugging Fees: Eagle River Energy Corporation  
 State of Oklahoma County, Tulsa, ss.  
Mark P. Godsey, President  Employee of Operator or  Operator on above-described well,  
 (Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mark P. Godsey

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



PO BOX 31 Russell, KS 67665

# INVOICE

Invoice Number: 123800

Invoice Date: Jul 30, 2010

Page: 1

Voice: (785) 483-3887

Fax: (785) 483-5566

<b>Bill To:</b>
Eagle River Energy Corporation 82A West Hwy 4 Hoisington, KS 67544

Customer ID	Well Name # or Customer #	Payment Terms	
EaRi	Maag #3	Net 30 Days	
Job Location	Camp Location	Service Date	Due Date
KS2-03	Russell	Jul 30, 2010	8/29/10

Quantity	Item	Description	Unit Price	Amount
165.00	MAT	Class A Common	13.50	2,227.50
110.00	MAT	Pozmix	7.55	830.50
9.00	MAT	Gel	20.25	182.25
4.00	MAT	Cottonseed Hulls	31.05	124.20
450.00	SER	handling	2.25	1,012.50
10.00	SER	Mileage 450 sx @ .10 per sk per mi	45.00	450.00
1.00	SER	Plug to Abandon	875.00	875.00
10.00	SER	Pump Truck Mileage	7.00	70.00

**GREATBEND DISTRICT**

LEASE/WELL NO. MAAG #3

PROPERTY NO. 100023

LOE 9788

AFE \_\_\_\_\_

OTHER \_\_\_\_\_

APPROVAL [Signature]

COMPANY NO. \_\_\_\_\_ VENDOR NO. \_\_\_\_\_

ALL PRICES ARE NET, PAYABLE 30 DAYS FOLLOWING DATE OF INVOICE. 1 1/2% CHARGED THEREAFTER. IF ACCOUNT IS CURRENT, TAKE DISCOUNT OF

**WICHITA**

ONLY IF PAID ON OR BEFORE

Aug 24, 2010

Subtotal	5,771.95
Sales Tax	479.07
Total Invoice Amount	6,251.02
Payment/Credit Applied	
<b>TOTAL</b>	<b>6,251.02</b>

RECEIVED  
AUG 16 2010  
KCC WICHITA

# ALLIED CEMENTING CO., LLC. 041574

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell

DATE <u>7-30-10</u>	SEC. <u>7</u>	TWP. <u>15</u>	RANGE <u>13</u>	CALLED OUT	ON LOCATION	JOB START <u>12:00</u>	JOB FINISH <u>12:30</u>
LEASE <u>Mary</u>		WELL # <u>3</u>		LOCATION <u>Russell + 280 S to River</u>		COUNTY <u>Russell</u>	STATE <u>KS</u>
<input checked="" type="checkbox"/> OLD OR NEW (Circle one)				<u>Bridge S to Second Bridge 1E 15 1/2 E</u> <u>1/2 N 1/4 E Nint</u>			

CONTRACTOR ATS Well Service OWNER \_\_\_\_\_

TYPE OF JOB PTA

HOLE SIZE _____	T.D. _____
CASING SIZE <u>5 1/2</u>	DEPTH _____
TUBING SIZE <u>2 3/8</u>	DEPTH _____
DRILL PIPE _____	DEPTH _____
TOOL _____	DEPTH _____
PRES. MAX _____	MINIMUM _____
MEAS. LINE _____	SHOE JOINT _____
CEMENT LEFT IN CSG. _____	
PERFS. _____	
DISPLACEMENT _____	

CEMENT Used 275 450#bbls  
 AMOUNT ORDERED 450 60/40 4% Gel  
500#bbls

COMMON <u>165</u>	@ <u>13.50</u>	<u>2227.50</u>
POZMIX <u>110</u>	@ <u>7.55</u>	<u>830.50</u>
GEL <u>9</u>	@ <u>20.25</u>	<u>182.25</u>
CHLORIDE _____	@ _____	_____
ASC _____	@ _____	_____

<u>Hill</u>	RECEIVED	@ <u>31.05</u>	<u>124.20</u>
	AUG 16 2010	@ _____	_____
	KCC WICHITA	@ _____	_____
		@ _____	_____
		@ _____	_____
HANDLING <u>450</u>	@ <u>2.25</u>	<u>1,012.50</u>	
MILEAGE <u>+ 10 1/2 hrs</u>		<u>450.00</u>	
		TOTAL	<u>4836.95</u>

**REMARKS:**

850' Mixed 200 sks then mixed  
Another 50 sks with 450# bbls.  
To Circulate Cement Mixed  
25 sks down 5 1/2" + Shut  
in @ 300psi

**SERVICE**

DEPTH OF JOB _____	
PUMP TRUCK CHARGE _____	<u>875.00</u>
EXTRA FOOTAGE _____	@ _____
MILEAGE <u>10</u>	@ <u>7.00</u> <u>70.00</u>
MANIFOLD _____	@ _____
_____	@ _____
_____	@ _____

TOTAL 995.00

**PLUG & FLOAT EQUIPMENT**

_____	@ _____
_____	@ _____
_____	@ _____
_____	@ _____
_____	@ _____

TOTAL \_\_\_\_\_

SALES TAX (If Any) \_\_\_\_\_

TOTAL CHARGES                     

DISCOUNT                      IF PAID IN 30 DAYS

CHARGE TO: Eagle River  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

Thanks!

To Allied Cementing Co., LLC.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME George Rice

SIGNATURE George Rice