

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Herman L. Loeb, LLC

Address: P O Box 524

Phone: (618) 943-2227 Operator License #: 3273

Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 5/18/10 (Date)

by: Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Morrow Depth to Top: 5,691 Bottom: 5,697 T.D. 5,800

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-175-20296-00-00

Lease Name: Colburn

Well Number: 7-63

Spot Location (QQQQ): _____ - SW - SE - SW

330 Feet from North / South Section Line

1625 Feet from East / West Section Line

Sec. 20 Twp. 33 S. R. 32 East West

County: Seward

Date Well Completed: 8/17/76

Plugging Commenced: 5/21/10

Plugging Completed: 5/25/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Morrow	Gas	5,691	5,697	8 5/8"	1,639'	none
				4 1/2"	5,752'	1,720'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RIH w/ tbg to 5674', spot 5 bbl of gel w/ 15#/bbl cottonseed hulls followed by 25 sk cement w/ 15#/bbl of hulls. POH w/ tbg.

Cut 4 1/2" casing @ 1720', w/ end of csg @ 1660', load hole w/ 92 bbl of fresh water gel, spot 50 sk of cement @ 1660'.

Pull casing to 500', spot 50 sk of cement @ 500', pull casing to 40', w/ end of csg @ 40', circulate the hole full using 50 sk of cement.

Pull last jt of csg, cement @ surface. The next morning, run 1" tbg & tag cement @ 100', pump 50 sk of cement fill 8 5/8".

Name of Plugging Contractor: Basic Energy Services License #: 32453

Address: 100 S Main St, Suite 607, Wichita, KS 67202

Name of Party Responsible for Plugging Fees: Herman L. Loeb, LLC

State of Illinois County, Lawrence, ss.

George Payne (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) George A. Payne

(Address) P. O. Box 838 Lawrenceville, IL 62439



Nancy L Huff
Notary Public

RECEIVED
AUG 18 2010
KCC WICHITA

_____ before me this 16th day of August, 20 10

My Commission Expires: 5/8/11