



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-167-21435-00-00

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Deenahan of Emphasis Oil Operations has this date requested permission to plug the following described well:

Mr. Deenahan guarantees payment of the plugging fee.

Operator's full Name: N-B Co., Inc.

Complete Address: Box 506 Russell, Kansas 67665

Lease Name: Bachar Well No. 1

Location: SE SE NW Sec. 5 Twp. 13 Rge. 13 ~~(E)~~ (W) X

County: Russell Total Depth 3420' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Deenahan was instructed to plug the well as follows:

Fill hole with mud and spot 50 sx cement at 480'.

Fill hole with mud and spot 25 sx cement at 240'.

Fill hole with mud to 40' and 1/2 sx hulls, plug, and 10 sx cement. 5 sx cement in rat hole.

252' of 8 5/8" surface casing cement circ.

Very truly yours,

Deann Rankin
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

MAR 20 1980
03-20-1980
CONSERVATION DIVISION
Wichita, Kansas