

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 9 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Holmstrom of K.N.N. G. has this

date requested permission to plug the following described well:

Mr. Holmstrom guarantees payment of the plugging fee.

Operator's full Name: Kansas Nebraska Natural Gas Co., Inc.

Complete Address: 300 N. St. Joseph Ave., Hastings, Nebraska

Lease Name: Englert Well No. 1

Location: C SE Sec. 26 Twp. 25 Rge. 39 XX (E) (W)

County Hamilton Total Depth 3060' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Holmstrom was instructed to plug the well as follows:

8 5/8" to 302' circulated w/ cement. 5 1/2" to 3058' cemented.

Top perforations 2464' Plug bottom w/ 20 sacks cement

Top of cement 2211' Mud 2211' to 350'

Spotted 35 sacks 350' to 250' Mud 250' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'

Very truly yours,

Edward J. Evans
Conservation Division Agent