

State of Kansas



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

#### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Tom Aum of Pioneer Drilling Co., Inc. has this  
date requested permission to plug the following described well:

Operator's Full Name: Liberty Enterprises, Inc.

Complete Address: 308 W. Mill St., Plainville, Ks. 67663

Lease Name: Nadel-Gussman Well No. #1

Location: SW NE NW Sec. 34 Twp. 11 Rge. 16 (E) (W)

County: Ellis Total Depth: 3410'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Aum was instructed to plug the well as follows:

8 5/8"-955' s.p. cuc. w/375 sacks 60/40 posmix-3% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 310' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulate 10 sacks of cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

FFR - 2 1982

Very truly yours,

CONSERVATION DIVISION  
Wichita, Kansas

*[Handwritten Signature]*  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION

2-2-1982  
FEB - 2 1982

CONSERVATION DIVISION  
Wichita, Kansas