

State of Kansas



15-051-22631-00-00

FORM CP-2

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
3-1-1982  
MAR 1 1982

CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Tom Aom of Pioneer Drilling Co., Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Liberty Enterprises, Inc.

Complete Address: 308 West Mill, Plainville, Ks. 67663

Lease Name: Orlan Cormichael Well No. 5

Location: NW NW NE Sec. 4 Twp. 11 Rge. 17 (E) (W)

County: Ellis Total Depth: 3700'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A xxx

Other well as hereafter indicated: \_\_\_\_\_

Mr. Aom was instructed to plug the well as follows:

8 5/8"-249' S.P. cuc. W/ 159 sacks common-2% Gel.-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. and 8 5/8" plug.

Spot W/ drill stem W/ heavy mud between all plugs.


1st plug at 750' W/ 70 sacks cement

2nd plug at 240' W/ 40 sacks cement

3rd plug-solid bridge of hulls and plug at 40' W/ 10 sacks cement.

Circulate 10 sacks in rat hole.

Very truly yours,

  
Conservation Division Agent