

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED

JUL 12 2010

Form CP-4 March 2009

Type or Print on this Form Form must be Signed All blanks must be Filled

KCC WICHITA

OPERATOR: License #: 34351 Name: Maralex Resources, Inc. Address 1: P.O. Box 338 City: Ignacio State: CO Zip: 81137 Contact Person: Doris Ney Phone: (970) 563-4000 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (If needed attach another sheet) Arbuckle Depth to Top: 3463 Bottom: T.D. 3550

API No. 15 - 163-23858-00-00 Spot Description: NE NE SE Sec. 36 Twp. 6 S. R. 18 East West 2,310 Feet from North South Line of Section 330 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Rooks Lease Name: Frances Stout Well #: 1-36 Date Well Completed: N/A The plugging proposal was approved on: 5/6/10 (Date) by: Pat Staab (KCC District Agent's Name) Plugging Commenced: 5/7/10 Plugging Completed: 5/7/10

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Formation, Content, Casing, Size, Setting Depth, Pulled Out. Row 1: Arbuckle, Oil, surface, 8-5/8", 297'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Logs were sent directly from logger. ACO-1 to be filed. Well not completed as logs showed no production potential.

Plugging procedure: Drill to TD of 3550'. Circ. and cond. mud. Run survey. TOH w/bit. RU loggers. Run full suite of logs from TD to surface csg. shoe. RD loggers. TIH w/ collars, LD collars. TIH open-ended w/DP. RU centers. Mix & pump 25 sk plug of 60/40 poz w/4% gel & 1/4# Floseal/sk cmt. Pump to top of Arbuckle. TOH LD 68 jts DP

Plugging Contractor License #: 33493 Name: American Eagle Drilling, LLC Address 1: 700 S. Washington Address 2: P.O. Box 66 City: Plainville State: KS Zip: 67663 Phone: (785) 434-2079 Name of Party Responsible for Plugging Fees: Maralex Resources, Inc. State of Colorado County: LaPlata, ss. Doris Ney (Print Name) Employee of Operator or Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Handwritten Signature]