

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 32278 Name: Tengasco, Inc. Address 1: P.O. Box 458 City: Hays State: KS Zip: 67601 Contact Person: Gary Wagner Phone: (785) 625-6374 Type of Well: Oil Well Is ACO-1 filed? Yes Producing Formation(s):

API No. 15 - 145-21,361-0000 Spot Description: SE NW NW Sec. 24 Twp. 20 S. R. 16 East West 4,290 Feet from North South Line of Section 4,290 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Pawnee Lease Name: Oetkin Well #: 5 Date Well Completed: The plugging proposal was approved on: 06/18/2010 by: Richard Lacey Plugging Commenced: 06/21/2010 Plugging Completed: 06/22/2010

Show depth and thickness of all water, oil and gas formations.

Table with 2 main columns: Oil, Gas or Water Records and Casing Record (Surface, Conductor & Production). Includes rows for Surface and Production casings with details on size, setting depth, and pulled out length.

RECEIVED JUL 09 2010 KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

06/21/10 - Drive to location. Wait on pits to get dug. Rig up. Set casing jacks. Bail 5 sacks cement on top of sand. Pull stretch on casing - 6-1/4". Shut down for day.

006/22/10 - Drive to location. Rig up Log-Tech. Shot casing off @ 1598'. Pulled 12 jts of 5-1/2" casing to 1120'. Line pit w/liner. Wait on cementers - 1 hour. 1st plug @ 1120', 15 sacks gel - 50 sacks cement 60/40 4%. Pull 17 jts to 400'. 2nd plug - 40 sacks cement. Pull 10 jts. Top off w/20 sacks. Total of 39 jts of 5-1/2". Rack out jacks. Rig down. Clean tools and location.

Plugging Contractor License #: 6901 Name: D.S. & W. Well Servicing, Inc. Address 1: 1822 24th Street City: Great Bend State: Kansas Zip: 67530 Phone: (620) 793-5838

Name of Party Responsible for Plugging Fees: Tengasco, Inc. State of Kansas County: Barton ss. Tim Dickson Employee of Operator or Operator on above-described well

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Tim Dickson