

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 6883 Name: Robinowitz Oil Company Address 1: 4200 E Skelly Drive, Sutie 620 City: Tulsa State: OK Zip: 74135 + 3210 Contact Person: C.E. Son Phone: (918) 481-7130 Type of Well: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (If needed attach another sheet) Depth to Top: Bottom: T.D.

API No. 15 - 167-19229 0000 Spot Description: SE NE SE Sec. 32 Twp. 15 S. R. 11 East West 990 1650 Feet from North South Line of Section 330 330 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Russell Lease Name: Davidson Well #: 2 Date Well Completed: 1962 The plugging proposal was approved on: 08/26/2010 (Date) by: Case Morris (KCC District Agent's Name) Plugging Commenced: 08/26/2010 Plugging Completed: 08/26/2010

Show depth and thickness of all water, oil and gas formations.

Table with 2 main columns: Oil, Gas or Water Records and Casing Record (Surface, Conductor & Production). Sub-columns include Formation, Content, Casing, Size, Setting Depth, and Pulled Out.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

08/26/10 - Drive to location. Wait on pits being dug. Rig up. Run sand line in - tag bottom @ 3275'. Wait on perforators - 1 hr. Rig up Log-Tech. Perf @ 1400', 700', 450', 150'. Rig Log-Tech down. Wait on welder - 1 hr. Run 104 - jts of 2-3/8" tubing. 1st plug @ 3224' w/12 sacks gel - 50 sacks 60/40 4% gel w/200# Hulls. 2nd plug @ 1400' w/130 sacks 60/40 4% gel w/300# Hulls. 3rd plug @ 700' w/25 sacks 60/40 4% gel w/100# Hulls. Pull tubing pump down casing w/90 sacks of 60/40 4% gel. Rig down. Clean tools & location. **Plugged back w/tubing

Plugging Contractor License #: 6901 Name: D.S. & W. Well Servicing, Inc. Address 1: 1822 24th Street Address 2: City: Great Bend State: Kansas Zip: 67530 Phone: (620) 793-5838 Name of Party Responsible for Plugging Fees: Robinowitz Oil Company State of Kansas County: Barton, ss. Tim Dickson (Print Name) Employee of Operator or Operator on above-described well

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Tim Dickson

RECEIVED SEP 02 2010

KCC WICHITA