

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 6931 Name: Bowman Oil Company Address 1: 805 Codell Road City: Codell State: Kansas Zip: 67663 Contact Person: Louis "Don" Bowman or William "Bill" Bowman Phone: (785) 434-2286 M-F

Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: Plugged Well SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet) Arbuckle Depth to Top: 3685' Bottom: 3693' T.D. 3693'

API No. 15 - 163-02175-0001 Spot Description: SW/4 of S22-T10S-R20W NE SW SW Sec. 22 Twp. 10 S. R. 20 East West 990 Feet from North South Line of Section 4,290 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW

County: Rooks County, Kansas Lease Name: Rogers Well #: 2 Date Well Completed: (July 5, 1954-original) June 15, 2010 The plugging proposal was approved on: June 15, 2010 (Date) by: District #4 - Rich Williams (KCC District Agent's Name) Plugging Commenced: June 15, 2010 Plugging Completed: June 15, 2010

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Row 1: Arbuckle, Oil & Water, Surface, 8 5/8", 202', 0. Row 2: Production, 5 1/2", 3687', 0.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Well was Plugged According to KCC-District #4's Instructions. Mixed 115 sacks with 200# Hulls @ 1300' to circulate cement to Surface. Pulled out of hole, Mixed 25 sacks cement to top off 5 1/2". Total of 140 sacks 60/40 Pox Mix, 4% Gel & 200 #'s Hulls. Got out of Hole at 1300' - Plugged well.

Plugging Contractor License #: Name: Allied Cementing Company, LLC Address 1: 24 S. Lincoln Street Address 2: P.O. Box 31 City: Russell State: Kansas Zip: 67665 Phone: (785) 483-2627

Name of Party Responsible for Plugging Fees: Bowman Oil Company State of Kansas County, Rooks, ss. Connie Jo Austin - Agent for Bowman Oil Company Employee of Operator or Operator on above-described well

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Connie Jo Austin

RECEIVED JUL 01 2010 KCC WICHITA