

Handwritten signature

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 34318
Name: Berexco, L.L.C.
Address 1: P. O. Box 723
Address 2: P. O. Box 20380, Wichita, KS 67206
City: Hays State: KS Zip: 67601 + _____
Contact Person: Mark Leiker
Phone: (785) 628-6101
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
4029 Depth to Top: 4036 Bottom: 3922 T.D. 3926
3990 Depth to Top: 3998 Bottom: 3912 T.D. 3916
3967 Depth to Top: 3972 Bottom: 3832 T.D. 3835

API No. 15 - 065-22449 0000 *✓*
Spot Description: _____
NE NE NE Sec. 3 Twp. 10 S. R. 25 East West
4,950 Feet from North / South Line of Section
330 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Graham
Lease Name: Shoemaker Well #: 1
Date Well Completed: 4-1988
The plugging proposal was approved on: 5/26/10 (Date)
by: Case Morris (KCC District Agent's Name)
Plugging Commenced: 6/13/10
Plugging Completed: 6/15/10 6/25/2010 *or see*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8	229	0
		Production	4 1/2	4079	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run tbg to 3900', mix 7 sx gel and 90 sx 60/40 4% gel w/300# hulls. Pull tbg to 1800' mix 100 sx 60/40 4% gel and circulate cement to surface. TOH w/tbg. Top off 4 1/2 casing w/40 sx 60/40 4% . Hook up to 8 5/8 and pump 5 sx, PSI to 200# and shut in. Rig down.

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 01 2010

Plugging Contractor License #: 34318 Name: Berexco, L.L.C.
Address 1: P. O. Box 723 Address 2: P. O. Box 20380, Wichita, KS 67206
City: Hays State: KS Zip: 67601 + _____
Phone: (785) 628-6101
Name of Party Responsible for Plugging Fees: Berexco, L.L.C.
State of Kansas County, Sedgwick, ss.

Mark Leiker *(Print Name)* Employee of Operator or Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mark Leiker