

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED

JUL 14 2010

KCC WICHITA

Form CP-4 March 2009

Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 31783 Name: Mid-Continent Energy Operating Co. Address 1: 100 W 5th St ste 450 Address 2: City: Tulsa State: OK Zip: 74103 + 4254 Contact Person: Grant M. Canaday Phone: (918) 587-6363 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (If needed attach another sheet) Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D.

API No. 15- 181-20560-00-00 Spot Description: NE SW SE NE Sec. 11 Twp. 7 S. R. 39 East West 2,127 Feet from North South Line of Section 832 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Sherman Lease Name: Yarger Well #: 1-11 Date Well Completed: 5/23/10 The plugging proposal was approved on: 5/17/10 (Date) by: David Wann (KCC District Agent's Name) Plugging Commenced: 5/24/10 @ 12:00 am Plugging Completed: 5/24/10 @ 4:30 am

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Row 1: Surface, 8 5/8, 344, None.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Commenced cementing 5/24/10 @ 12:00 am. 1st plug: 25sx @ 3160', 2nd plug: 100sx @ 2250', 3rd plug: 40sx @ 390', 4th plug: 10sx @ 40', 30sx in the rathole, 15sx in the mousehole. Total of 220sx of 60/40 poz - 4% gel - 1/4# per sx flo-seal. Drilling mud was placed between all stages. Cementing complete 5/24/10 @ 4:30 am, by Allied Cementing.

Plugging Contractor License #: 33575 Name: WW Drilling, LLC Address 1: 233 S. 4th Address 2: PO Box 307 City: Wakeeney State: KS Zip: 67672 Phone: (785) 743-6774

Name of Party Responsible for Plugging Fees: Mid-Continent Energy Operating Co. State of OK County, Tulsa, ss. Grant M. Canaday (Print Name) Employee of Operator or Operator on above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Handwritten Signature]

WW Drilling, LLC
WaKeeney, KS
Well Plugging Orders

Operator: Mid-Continent Energy Operating Company License # 31783
Address: 100 W. 5th Street, Ste 450 - Tulsa, Oklahoma 74103

API # 15-181-20560-00-00

Lease Name: Yarger # 1-11
Legals: 227' FNL & 832' FEL, Section 11-7s-39w
County: Sherman
State: Ks

Plug #	Sx.	@	Feet
1st	<u>25</u>	<u>@</u>	<u>3160</u>
2nd	<u>100</u>	<u>@</u>	<u>2250</u>
3rd	<u>40</u>	<u>@</u>	<u>390</u>
4th	<u>10</u>	<u>@</u>	<u>40</u>
5th		<u>@</u>	
Rathole	<u>30</u>		
Mousehole	<u>15</u>		

Total: 220

Type: 60/40 Poz - 4% Gel - 1/4 # per sx flo-seal

RECEIVED
JUL 14 2010
KCC WICHITA

Spud Report: Marvin Mills Date: 5/12/2010 Time: 10:15 AM

Orders From: David Wann Date: 5/17/2010 Time: 10:45 AM

Reported to: Marvin Mills Date: 5/25/2010 Time: 3:00 PM

Results: D & A Allied Cementing

ALLIED CEMENTING CO., LLC. 039256

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
OAKLE, KS

DATE <u>5-23-10</u>	SEC. <u>11</u>	TWP. <u>7S</u>	RANGE <u>29W</u>	CALLED OUT	ON LOCATION <u>10:00pm</u>	JOB START <u>4:00AM</u>	JOB FINISH <u>4:30AM</u>
LEASE <u>4-15-08</u>	WELL# <u>1-11</u>	LOCATION <u>Goodland Rm-2" 26</u>			COUNTY <u>Sherman</u>	STATE <u>KS</u>	

OLD OR NEW (Circle one) NEW

CONTRACTOR <u>W-W-2</u>	OWNER
TYPE OF JOB <u>PTA</u>	CEMENT
HOLE SIZE <u>7 7/8</u> TD. <u>5273'</u>	AMOUNT ORDERED <u>220 SKS 60120</u>
CASING SIZE DEPTH	<u>49000 114+ Plusport</u>
TUBING SIZE DEPTH	
DRILL PIPE DEPTH <u>3160</u>	
TOOL DEPTH	
PRES. MAX MINIMUM	COMMON <u>132 @ 15" 2039 40</u>
MEAS. LINE SHOE JOINT	POZMIX <u>88 @ 8 704 00</u>
CEMENT LEFT IN CSG.	GEL <u>8 @ 200 166 00</u>
PERFS.	CHLORIDE @
DISPLACEMENT	ASC @

EQUIPMENT

PUMP TRUCK CEMENTER <u>Fuss</u>
<u>431</u> HELPER <u>Pully</u>
BULK TRUCK
<u>377</u> DRIVER <u>Sperry</u>
BULK TRUCK
DRIVER

RECEIVED	
JUL 14 2010	
KCC WICHITA	
HANDLING <u>230 @ 2 49 552 00</u>	
MILEAGE <u>110 x 5 km 10 1380 00</u>	
TOTAL <u>4970 30</u>	

REMARKS:

25 sks @ 3160

100 sks @ 2250

40 sk @ 290

10 sk @ 40

30 sk P/B

15 sk MH

Job done at 4:30am

THANKS TRUSSARD

SERVICE

DEPTH OF JOB <u>3160'</u>
PUMP TRUCK CHARGE <u>1185 00</u>
EXTRA FOOTAGE @
MILEAGE <u>60 @ 42 420 00</u>
MANIFOLD @
@
@
TOTAL <u>1605 00</u>

CHARGE TO: Mid Continent Energy Operations

STREET _____

CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

<u>1 Dry hole plug @ 40 00</u>
@
@
@
TOTAL <u>40 00</u>

To Allied Cementing Co., LLC.
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME _____

SIGNATURE Dale Brunick

SALES TAX (If Any) _____

TOTAL CHARGES _____

DISCOUNT _____ IF PAID IN 30 DAYS

ALLIED CEMENTING CO., LLC. 039246

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
QAEPS

DATE <u>5.17.10</u>	SEC <u>11</u>	TWP. <u>17</u>	RANGE <u>39</u>	CALLED OUT	ON LOCATION <u>7 am</u>	JOB START <u>12:30am</u>	JOB FINISH <u>1:00am</u>
LEASE <u>Y 050K</u>		WELL # <u>1-1</u>	LOCATION <u>Goodland Twp mm 170</u>			COUNTY <u>Shoemaker</u>	STATE <u>KS</u>
OLD OR <u>NEW</u> (Circle one)		<u>312 0 2</u>					

CONTRACTOR W. W. #2

TYPE OF JOB Surface

HOLE SIZE 12 1/4" T.D. 345'

CASING SIZE 8 1/2" DEPTH 345'

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. 15

PERFS. _____

DISPLACEMENT 21.0

OWNER _____

CEMENT AMOUNT ORDERED 240 cov 390cc

290cc

COMMON	<u>240</u>	@	<u>15.45</u>	<u>3708.00</u>
POZMIX		@		
GEL	<u>5</u>	@	<u>20.80</u>	<u>104.00</u>
CHLORIDE	<u>8</u>	@	<u>58.20</u>	<u>465.60</u>
ASC		@		

EQUIPMENT

PUMP TRUCK CEMENTER Fuzzie

431 HELPER Kelly

BULK TRUCK

377 DRIVER Damon

BULK TRUCK

_____ DRIVER _____

RECEIVED

JUL 14 2010

KCC WICHITA

HANDLING	<u>253</u>	@	<u>2.40</u>	<u>607.20</u>
MILEAGE	<u>1043.24</u>	@	<u>1.50</u>	<u>1564.86</u>
TOTAL				<u>6402.00</u>

REMARKS:

removed old annular cements

in collar

job completed @ 1:00am

Thanks Fuzzie

SERVICE

DEPTH OF JOB	<u>345'</u>		
PUMP TRUCK CHARGE		@	<u>1018.00</u>
EXTRA FOOTAGE	<u>45</u>	@	<u>.85</u> <u>38.25</u>
MILEAGE	<u>60</u>	@	<u>7.50</u> <u>450.00</u>
MANIFOLD		@	

CHARGE TO: Mid-Continent Energy Operations

STREET _____

CITY _____ STATE _____ ZIP _____

TOTAL 1438.00

PLUG & FLOAT EQUIPMENT

_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
TOTAL _____		

To Allied Cementing Co., LLC.
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME Jay Schneider

SIGNATURE Jay Schneider

SALES TAX (If Any) _____

TOTAL CHARGES _____

DISCOUNT _____ IF PAID IN 30 DAYS