

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form CP-1
March 2010

This Form must be Typed
Form must be Signed
All blanks must be Filled

WELL PLUGGING APPLICATION

Form KSONA-1, Certification of Compliance with the Kansas Surface Owner Notification Act,
MUST be submitted with this form.

OPERATOR: License #: 3880
Name: KC Resources, Inc.
Address 1: P.O. Box 6749
Address 2: _____
City: Snowmass Village State: CO Zip: 81615 + _____
Contact Person: Tony Shumsky
Phone: (970) 927-2764

API No. 15 - 095-00505 - 0001
If pre 1967, supply original completion date: 5/1/1962
Spot Description: _____
C SW NW Sec. 27 Twp. 28 S. R. 7 East West
3,300 Feet from North / South Line of Section
4,620 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Kingman OWWD
Lease Name: Alameda Unit A Well #: 6-3

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8 5/8" Set at: 265' Cemented with: 240 Sacks
Production Casing Size: 4 1/2 Set at: 4443' Cemented with: 200 Sacks

List (ALL) Perforations and Bridge Plug Sets:
LKC 3703-3708 sqzd; MISS 3992-3996 sqzd; Viola 4364-4366; Viola 4371-4375; Simp 4385-4388

Elevation: 1617 (G.L. / K.B.) T.D.: 4444' PBTD: 4400' Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Junk in Hole Casing Leak at: _____
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):
Perf 4 1/2" csg @ 2,500', spot a 50 sx plug w/common cement. Tag plug.
Perf 4 1/2" csg @ 1,075', spot a 35 sx plug w/common cement. Tag plug.
Perf 4 1/2" csg @ 675', spot a 35 sx plug w/common cement. Tag plug.
Perf 4 1/2" csg @ 315', circ. common cement up backside to surface. Cement 4 1/2" csg from 315' to surface w/common cement.

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No
If ACO-1 not filed, explain why:

RECEIVED
SEP 22 2010
KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Jim Kraft
Address: 1579 NE 140th Avenue City: Clafin State: KS Zip: 67525 + _____
Phone: (620) 388-2356
Plugging Contractor License #: 99996 Name: Allied Cementing Co., LLC
Address 1: P.O. Box 368 Address 2: _____
City: Medicine Lodge State: KS Zip: 67104 + _____
Phone: (620) 886-5926
Proposed Date of Plugging (if known): 9-22-10

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 9-21-10 Authorized Operator / Agent: Anthony C Shumsky
(Signature)

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

**CERTIFICATION OF COMPLIANCE WITH THE
KANSAS SURFACE OWNER NOTIFICATION ACT**

Form KSONA-1
July 2010
Form Must Be Typed
Form must be Signed
All blanks must be Filled

This form must be submitted with all Forms C-1 (Notice of Intent to Drill); CB-1 (Cathodic Protection Borehole Intent); T-1 (Request for Change of Operator Transfer of Injection or Surface Pit Permit); and CP-1 (Well Plugging Application). Any such form submitted without an accompanying Form KSONA-1 will be returned.

Select the corresponding form being filed: C-1 (Intent) CB-1 (Cathodic Protection Borehole Intent) T-1 (Transfer) CP-1 (Plugging Application)

OPERATOR: License # 3880
Name: KC Resources, Inc.
Address 1: P.O. Box 6749
Address 2: _____
City: Snowmass Village State: CO Zip: 81615 + _____
Contact Person: Tony Shumsky
Phone: (970) 927-2764 Fax: (970) 927-3862
Email Address: tshumsky@crystalriveroil.com

Well Location:
C SW NW Sec. 27 Twp. 28 S. R. 7 East West
County: Kingman
Lease Name: Alameda Unit Well #: 6-3

If filing a Form T-1 for multiple wells on a lease, enter the legal description of the lease below:

Surface Owner Information:

Name: Margie Leckler Trust c/o Debra Webber
Address 1: 1050 SE 50th St.
Address 2: _____
City: Kingman State: KS Zip: 67006 + _____

When filing a Form T-1 involving multiple surface owners, attach an additional sheet listing all of the information to the left for each surface owner. Surface owner information can be found in the records of the register of deeds for the county, and in the real estate property tax records of the county treasurer.

If this form is being submitted with a Form C-1 (Intent) or CB-1 (Cathodic Protection Borehole Intent), you must supply the surface owners and the KCC with a plat showing the predicted locations of lease roads, tank batteries, pipelines, and electrical lines. The locations shown on the plat are preliminary non-binding estimates. The locations may be entered on the Form C-1 plat, Form CB-1 plat, or a separate plat may be submitted.

Select one of the following:

I certify that, pursuant to the Kansas Surface Owner Notice Act (House Bill 2032), I have provided the following to the surface owner(s) of the land upon which the subject well is or will be located: 1) a copy of the Form C-1, Form CB-1, Form T-1, or Form CP-1 that I am filing in connection with this form; 2) if the form being filed is a Form C-1 or Form CB-1, the plat(s) required by this form; and 3) my operator name, address, phone number, fax, and email address.

I have not provided this information to the surface owner(s). I acknowledge that, because I have not provided this information, the KCC will be required to send this information to the surface owner(s). To mitigate the additional cost of the KCC performing this task, I acknowledge that I am being charged a \$30.00 handling fee, payable to the KCC, which is enclosed with this form.

If choosing the second option, submit payment of the \$30.00 handling fee with this form. If the fee is not received with this form, the KSONA-1 form and the associated Form C-1, Form CB-1, Form T-1, or Form CP-1 will be returned.

I hereby certify that the statements made herein are true and correct to the best of my knowledge and belief.

Date: 9-21-10 Signature of Operator or Agent: [Signature] Title: Asst Land Mgr

RECEIVED
SEP 22 2010

**Crystal River Oil and Gas
Well Alameda 6-3
Kingman Co, KS**

Proposed PA Procedure

1. Move in, rig up.
2. GIH w perforating gun and perforate the following intervals with 4 JSPF: 2500', 1075', 675' and 315'. 4 int, 16 holes.
3. GIH w workstring and spot 50sx Cl A cmt w/3%CaCl @2500'. Tag per KCC.
4. Pull workstring up 1000' and WOC 1 hr.
5. GIH w/workstring and tag cement. Pull up and spot 35sx Cl A cmt w/3%CaCl @1075'. Tag per KCC.
6. POH and WOC 1 hr.
7. GIH w/workstring and tag cement. Pull up and spot 35sx Cl A cmt w/3%CaCl @400-870'(Note: Plug size estimated 470 ft, 1.18 cuft/sx, 11.1 lin ft/cuft). Tag per KCC.
8. POH and WOC 1 hr.
9. GIH w/workstring and tag cement. POH.
10. Rig up pump truck to casing and pump to establish circulation 315'-surface. Pump 100 sx Cl A cmt w/3%CaCl.
11. Rig down and clean location.

Dan O Westover
Production Engineer
Consultant
Crystal River Oil and Gas
September 21, 2010

RECEIVED
SEP 22 2010
KCC WICHITA



Mark Parkinson, Governor Thomas E. Wright, Chairman, Joseph F. Harkins, Commissioner, Ward Loyd, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

KC RESOURCES, INC. DBA CRYSTAL RIVER
P. O. BOX 6749
SNOWMASS VILLAGE, CO 81615

September 22, 2010

Re: ALAMEDA UNIT OWWO #6-3
API 15-095-00505-00-01
27-28S-7W, 3300 FSL 4620 FEL
KINGMAN COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after March 21, 2011. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000