

KANSAS  
STATE CORPORATION COMMISSION  
15-051-05411-00-00  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

3-9-1964  
MAR 9 1964

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Colorado Oil & Gas  
Complete Address: Box 1030 Wichita, Kansas  
Lease Name Slimmer Well No. 1  
Location SW SW SE Sec. 11 Twp. 11 Rge. (E) (W) 17  
County Ellis Total Depth 3361  
Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated:       
Plugging Contractor: Knight Gasing Pulling  
Address: Chase, Kans License No. 436  
Operation Completed: Hour 4PM Day 4 Month 3 Year 64

The Above well, was plugged as follows:

8 5/8" 1009' circulated with cement - 5 1/2" 3361' with 100 sax cement - perf 3165'

Filled with sand to 3150', set 4 sax cement with dump bailer- pulled 2790' 5 1/2" to 800', circulated hole with heavy mud at 800' ( 17 sax Gel), displaced 25 sax cement through 5 1/2" at 500', heavy mud to 200', displaced 25 sax cement through 5 1/2" at 200', heavy mud to 35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Knight Company Pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edson Lee*  
Well Plugging Supervisor

DATE 3/10/64  
INV. NO. 8449-10