

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 1 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Sun Oil Company  
Complete Address 300 Security Life Building, Denver, Colorado 80202  
Lease Name Henderson Well No. 1  
Location SE SE NW Sec. 7 Twp. 11 Rge. (E) (W) 17  
County Ellis Total Depth 3519'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Reckhold Engineering  
Address Box 698 Great Bend, Kansas 67530 License No. 670  
Operation Completed: Hour 1:30 P Day 30 Month 1 Year 1974

The above well was plugged as follows:  
Total Depth 3519' 10 3/4 csg set at 1152' ewc 600 sk.  
7" csg set at 3413' ew 250 sk cmt.  
4 1/2" csg liner set(3385-3519) Perf. (3464).  
Set 7" weed plug at 3385' -poured 25' sand & dumped 5 sk cmt W/dump bailer. (3330-3385)  
Cutoff and recovered 2220' of 7" csg.  
Filled 10 3/4" csg with mud to 400' -set reek & sand bridge (400-375)  
Filled with readymix cement from 375' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey  
Well Plugging Supervisor

INVOICED

DATE 2/1/74  
INV. NO. 8486-W