

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 118-41

LOCATION SW SW NE

SEC. 7 TWP. 11 RGE. 17

Dry Hole *m* Abandoned Oil Well *X* Abandoned Gas Well

*ANB  
ECC*

I have this date completed supervision of plugging of:

Well No. ~~1~~ 1 Lease Henderson *A* *ANB  
ECC*

Operator Stanolind Oil & Gas Address Box 35 Gorham, Kans

Field  County Ellis

Total Depth 3450 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address Chase, Kans

(Describe briefly the manner in which the well was plugged)

15" at 78' circulated - 10 3/4" at 1164' circulated - 7" at  
3422' with 150 sax cement behind.

Tubing and fishing tools lost in hole, top of fish 2400', hole  
full mud to 2400'.

Pulled 2500' 7", pumped hole full mud (30) sax, pumped cementing  
plug to 200', followed by 100 sax cement, filling hole 200' to 0'  
with cement.

Mudding and Cementing by Halliburton Co. 500# pump pressure.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 20 1953  
10-20-53  
CONSERVATION DIVISION  
Wichita, Kansas

*Edwin Perry*  
District Conservation Agent

Date 10-19-53

**PLUGGING**  
FILE SEC. 2 T. 11 R. 12 W.  
BOOK PAGE 118-41-44