

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 6 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Sun Oil Company  
Complete Address 300 Security Life Building, Denver, Colorado 80202  
Lease Name Henderson Well No. 4  
Location C N/2 SE NW Sec. 7 Twp. 11 Rge. (E) (W) 17  
County Ellis Total Depth 3455'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated       

Plugging Contractor Reckhold Engineering  
Address Box 698 Great Bend, Kansas 67530 License No. 670  
Operation Completed: Hour 2 P Day 4 Month 2 Year 1974

The above well was plugged as follows:

Total Depth 3455' 16" csg 105' cwc 100 sk 10 3/4 csg 1142' cwc 600 sk.  
7" csg set at 3445' cw 250 sk.  
Filled 7" csg with sand (3445-3430) dumped 5 sk cmt W/dump bailer. (3410-3445)  
Cutoff and recovered 1920' of 7" csg.  
Filled 10 3/4 csg with mud to 426' -set reek & sand bridge (426-405)  
Filled with readymix cement from 405' to base of collar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey  
Well Plugging Supervisor

INVOICED

DATE 2/8/74  
INV. NO. 8544-W