

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

7090

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
JUN 12 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Clinton Oil Company

Complete Address 217 N. Water Wichita, Kansas 67202

Lease Name N. Henderson "A" Well No. 5

Location C W/2 SE NE Sec. 7 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3414'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 4 P Day 6 Month 6 Year 1973

The above well was plugged as follows:

Total Depth 3414' 10 3/4 csg set at 1130' cwc

7" csg set at 3411' cw 150 sk cmt.

Filled 7" csg W/sd (3381-3414) dumped 7 sk cmt W/dump bailer. (3350-3381)

Cutoff and recovered 2090' of 7" csg.

Mud to 400' -set rock & sand bridge (385-400)

Dumped 7 yds readymix cem. from 385' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Murray
Well Plugging Supervisor

DATE 6/12/73

INV. NO. 9491-W