

KANSAS

Form CP-3
Rev. 6-4-68

15-051-01695-00-00

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 27 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Sun Oil Company

Complete Address 300 Security Life Bldg., Denver, Colorado 80202

Lease Name Hendersen Well No. 5

Location C S/2 NE NW Sec. 7 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3493'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Reckhold Engineering

Address Box 698 Great Bend, Kansas 67530 License No. 670

Operation Completed: Hour 10 A Day 19 Month 2 Year 1974

The above well was plugged as follows:

Total Depth 3493' 16" csg 120' cw 100 sk 10 3/4 csg 1195' cwe 600 sk.

7" csg set at 3483' cw 250 sk.

4 1/2 csg liner set (3455-3550) & perf. (3497-3504)

Set 7" plug at 3455' -poured 10' sand -dumped 5 sk cmt W/dump bailer. (3515-3455)

Cutoff and recovered 2360' of 7" csg.

Filled 10 3/4 csg with mud to 450' -set reek & sand bridge (450-425)

Filled with readymix cement from 425' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Lud Z Massey
Well Plugging Supervisor

INVOICED
DATE 2/27/74
INV. NO. 8652-W