

KANSAS

FORM CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, Ks. 67202

API Number 15 - (OWWO) (of this well)

Operator's Full Name LIBERTY ENTERPRISES, INC.

Complete Address 308 WEST MILL, PLAINVILLE, KANS. 67663

Lease Name HENDERSON-COLLINS Well No. #5 - (OWWO)

Location C-5 1/2 - NE - NW Sec. 7 Twp. 11 Rge. 17 (E) (W) W

County ELLIS Total Depth 2060 ^{FE}

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated TWISTED OFF - LOST HOLE

Plugging Contractor PIONEER DRILLING INC.

Address 308 WEST MILL - PLAINVILLE, KS License No. _____

Operation Completed: Hour 11:00 ^{AM} Day 15 Month SEPT Year 1980

The Above well was plugged as follows:

LOST HOLE - TWISTED OFF - LOST APPROX 420 FE DRILL STEM IN HOLE
10 3/4" 1142 FE SP. CUC.

ORDERED 120 ST 50/50 POZMIX 6% GEL.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS
1 ST PLUG. @ 740 FE w/ 70 ST CNT.

2 ND PLUG. @ 300 FE w/ 30 ST CNT.

3 RD PLUG. - SPOTTED 15 ST CNT. @ 30 FE CIRCULATED TO TOP 1980

5 ST IN RAT HOLE CEMENTED BY ALLIED

RECEIVED
STATE CORPORATION COMMISSION
SEP 15 1980
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 9-17-80
INV. NO. 31642

Signed: M. Schmidt
Well Plugging Supervisor