

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAR 28 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sun Oil Company
Complete Address 300 Security Life Bldg., Denver, Colorado 80202
Lease Name Henderson Well No. 6
Location C N/2 SW NW Sec. 7 Twp. 11 Rge. (E) (W) 17
County Ellis Total Depth 3397'
Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Rockhold Engineering
Address Box 698, Great Bend, Kansas 67530 License No. 670
Operation Completed: Hour 1 P Day 27 Month 3 Year 1974

The above well was plugged as follows:

Total Depth 3397' 16" csg 115' cwc 100 sk 10 3/4 csg 1128' cwc 630 sk.

7" csg 3385' cw 250 sk cem.

5 1/2" liner set (3349'-3398') & cemented. Perf. (3393'-3397')

Set wood plug 3349' -poured 25' sand -dumped 5 sk cem W/dump bailer. (3300-3349)

Cutoff and recovered 2250' of 7" csg.

Filled 10 3/4 csg with mud to 385' -set rock & sand bridge (385'-360')

Filled with readymix cement from 360' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/28/74

INV. NO. 8833-10

Signed: Red A. Massey
Well Plugging Supervisor