

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 105-14

LOCATION CW $\frac{1}{2}$ NW NW

SEC. 7 TWP. 11 RGE. 17

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 7 Lease Henderson *B04661*

Operator Morgenstern-Specter Address Russell, Kans

Field _____ County Ellis

Total Depth 3447 Feet.

Plugging Contractor R & D Pipe Pulling

Plugging Contractor's License No. 236

Address _____

(Describe Briefly the manner in which the well was plugged)

10 3/4" at 1178' circulated with cement - 15" at 110' circulated
with cement - 7" at 3445' with 250 sax cement behind.

Lane Wells plugs to 3127' - perforated at 3167'.

Filled with sand to 3150', set 5 sax cement with dump bailer,
pulled 2460' 7" - heavy mud to 300', set rock and 25 sax cement,
mud to 30', set rock and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1956
10-15-56
CONSERVATION DIVISION
Wichita, Kansas

Edward Letty
District Conservation Agent

Date 10-14-56

PLUGGING
FILE SEC. 7 T. 11 R. 17W
BOOK PAGE 105 LINE 14