

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 25 1974  
03-25-74  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Sun Oil Company

Complete Address 800 Security Life Bldg., Denver, Colorado 80202

Lease Name Henderson Well No. 8

Location C. <sup>E/2</sup> S/2 NW NW Sec. 7 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth ~~XXXX~~ 3536'

Abandoned Oil Well XK Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Rockhold Engineering

Address Box 698 Great Bend, Kansas License No. 670

Operation Completed: Hour 12 N Day 22 Month 3 Year 1974

The above well was plugged as follows:

Total Depth 3536' 16" csg 118' CWW 100 sk. 10 3/4 csg 1197' CWC 625 sk.

7" csg set at 3460' cw 250 sk cem.

4 1/2 csg liner (3375-3536) & cemented. Perf. (3506 & 3507)

Set wood plug at 3375' -poured 25' sand -dumped 5 sk cem W/dump bailer. (3325-3375)

Cutoff and recovered 2330' of 7" csg.

Filled 10 3/4 csg with mud to 440' -set rock & sand bridge (440-425)

Filled with readymix cement from 425' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 3/28/74  
INV. NO. 8793-W

Signed: Leo F. Massey  
Well Plugging Supervisor